



15-179-20104-00+00

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 28 1968

CONSERVATION DIVISION  
Wichita, Kansas

5-28-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Norman Cook guarantees payment of the plugging fee.

Operator's full Name: Marmik Oil Company & Abercrombie Drilling, Inc.

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Mosier Well No. 1

Location: CSW-SW Sec. 33 Twp. 8 Rge. (E)(W) 27

County: Sheridan Total Depth 3125 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

253'--7" OD Surface casing, cement circulated with 125 Sx. (6 1/4" Hole).  
Top of Dakota section @ 1250'.

Circulate hole with heavy mud. Pull DP to 1425' and displace 60 Sx.  
cement thru DP. Pull DP to 275' and displace 15 Sx. cement thru DP.  
Pull DP to 35', set plug with 1/2 sack hulls and 5 Sx. cement to bottom  
of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent