



15-179-20102-00-00

ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 300 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 27 1968
 CONSERVATION DIVISION
 Wichita, Kansas

5-27-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: McKinney Well No. L

Location: CNE-NW Sec. 13 Twp. 8 Rge. (E)(W) 28

County: Sheridan Total Depth 4097 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

238'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Dakota section top @ 1200'.

Circulate hole with heavy mud. Pull DP to 1320' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. S. Nichols
 Conservation Division Agent