

State of Kansas



15-179-20027-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Co., has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 4th National Bank Bldg., Wichita, Kans.

Lease Name: Campbell Well No. 1

Location: CSE-SE Sec. 14 Twp. 8 Rge. (E)(W) 28

County Sheridan Total Depth 4450 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

249' -- 8 5/8" Surface pipe, cement circulated with 160 Sx. Dakota section from 1500' to 1730'.

Displace 100 Sx. cement thru DP. from 1750' to 1400'.

Pull DP. to 205' and displace 20 Sx. cement thru DP.

Pull DP. set plug with 1/2 sack hulls @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1967

7-19-67

CONSERVATION DIVISION
Wichita, Kansas