



15-179-20078-00-00

ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 12 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 3-12-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Sonny Denning of Dean & Clark, Incorporated, has this date requested permission to plug the following described well:

Mr. Denning guarantees payment of the plugging fee.

Operator's full Name: Dean & Clark, Incorporated,

Complete Address: 416 Union Center Building, Wichita, Kansas.

Lease Name: Schaffer Well No. 1

Location: CS/2-SE-SE Sec. 26 Twp. 8 Rge. (E)(W) 28


County: Sheridan Total Depth 4102 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Denning was instructed to plug the well as follows:

248'--8 5/8" Surface pipe, cement circulated.

Circulate hole with heavy mud. Pull DP to 1800' and displace 100 Sx. cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

 Conservation Division Agent