

State of Kansas



15-179-20173-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 13 1969
 CONSERVATION DIVISION
 Wichita, Kansas

1/13/69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated.

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: K. Clark Well No. 1

Location: NW-NW-NE Sec. 32 Twp. 8 Rge. (E)(W) 28

County: Sheridan Total Depth 3810 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

250'--7" OD Surface pipe, cement circulated with 100 Sx. (6 1/4" Hole), Dakota section top @ 1100'.

Circulate hole with heavy mud. Pull DP to 1310' and displace 65 Sx. cement thru DP. Pull DP to 275' and displace 15 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent