



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1973

CONSERVATION DIVISION
Wichita, Kansas

11-19-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Shaw Well No. C-1

Location: CSE-SE Sec. 33 Twp. 8 Rge. (E)(W) 28

County: Sheridan Total Depth 4050' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 175 Sx.
4049'--4 1/2" Production casing cemented with 175 Sx. Well plugged back
to 4016'. Top perforations from 3785' to 3788'.

Push plug to 3750', sand back to 3700' and set 5 Sx. cement with dump
bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks
gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent