



15-179-20219-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Armbruster of B & B Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Armbruster guarantees payment of the plugging fee.

Operator's full Name: Vannocker & Ropfogel

Complete Address: 515 Sutton Place, Wichita, Kansas

Lease Name: Shaw Well No. 1

Location: CNW-SE Sec. 33 Twp. 8 Rge. (E)(W) 28

County: Sheridan Total Depth 1100' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Armbruster was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1180'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 100 Sx.

cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.

Pull DP. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom

of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1969

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent