



15-179-20230-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Shaw Well No. C-2

Location: CSE-NW Sec. 35 Twp. 8 Rge. (E)(W) 28

County: Sheridan Total Depth 4090' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

~~Rowe~~ Mr. Rowe was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1175'.

Circulate hole with heavy mud. Pull DP to 1400' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 26 1969

CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

Conservation Division Agent

926-69