

State of Kansas



15-179-20160-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
12-2-68

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Schropp Well No. 1

Location: CSW-SW Sec. 34 Twp. 8 Rge. (E)(W) 28

County: Sheridan Total Depth 4020 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 220 Sx.  
Top of Dakota section @ 1150'.

Circulate hole with heavy mud. Pull DP to 1375' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*W. L. Nichols*

Conservation Division Agent