



15-179-20106-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas
6368

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Roy Cook of Imperial Oil Company has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: 780 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Selbe Well No. 1

Location: 440' FWL & 440' FNL-NE/4 Sec. 22 Twp. 8 Rge. (E)(W) 29

County: Sheridan Total Depth 2570' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

243'--8 5/8" Surface pipe, cement circulated with 200 Sx.
Dakota section top @ 1300'.

Circulate hole with heavy mud. Pull DP to 1525' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. S. Nichole

Conservation Division Agent