



15-179-20291-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
11-1-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. G. W. Nestlerode of Chief Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Nestlerode guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Company,

Complete Address: 117 Cameron Building, Oklahoma City, Oklahoma.

Lease Name: Edwards Well No. 1

Location: CNW-SE Sec. 26 Twp. 8 Rge. (E)(W) 29

County: Sheridan Total Depth 4100' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Nestlerode was instructed to plug the well as follows:

198'--8 5/8" Surface casing, cement circulated with 275 Sx.  
Top of Dakota section @ 1200'.

Circulate hole with heavy mud. Pull DP to 1425' and displace 100 Sx.  
cement thru DP. Pull DP to 225' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

A. L. Dickole  
Conservation Division Agent