



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Wilber Crandall of Knight Csg. Pulling Co. Inc., has this date requested permission to plug the following described well:

Mr. Crandall guarantees payment of the plugging fee.

Operator's full Name: Misco Supply Company,

Complete Address: Misco Building, Wichita, Kansas.

Lease Name: Edwards Well No. 1

Location: SW-SW-SE Sec. 26 Twp. 8 Rge. (E)(W) 29

County: Sheridan Total Depth 4360 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crandall was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 200 Sx.
4360'--4 1/2" Production casing cemented on bottom with 100 Sx. Well
plugged back to 4180'. Top perforation @ 4170'.

Sand well back to 4150' and set 3 sx. cement with dump bailer. Pull 4 1/2"
casing and squeeze well with 30 sacks gel plus 5 sacks hulls and 130 Sx.
cement staged.

RECEIVED
 STATE CORPORATION COMMISSION Very truly yours,

OCT 14 1968
 CONSERVATION DIVISION
 Wichita, Kansas

10-14-68

W. A. Nichols
 Conservation Division Agent