



15-179-20093-00-00

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 6 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
66-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Slaughter of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Slaughter guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name: Day Well No. 1

Location: SE-SE-SE Sec. 27 Twp. 8 Rge. (E)(W) 29

County: Sheridan Total Depth 3939 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Slaughter was instructed to plug the well as follows:

251'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
Top of Dakota section @ 1300'.

Circulate hole with heavy mud. Pull DP to 1525' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

Very truly yours,

Conservation Division Agent