

15-065-01361-00-00

API NUMBER 4-30-1951  
 LEASE NAME Clack  
 WELL NUMBER 2

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

990 Ft. from S Section Line  
3630 Ft. from E Section Line

LEASE OPERATOR Bowman Oil Company  
 ADDRESS 805 Codell Road Codell, Ks 67403  
 PHONE# (913) 434-7202 OPERATORS LICENSE NO. 6931

SEC. 9 TWP. 9 RGE. 21 (E) or (W)  
 COUNTY Graham

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 4-30-1951  
 Plugging Commenced 8-28-96  
 Plugging Completed 8-28-96

The plugging proposal was approved on 8-28-96 (date)  
 by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? YES if not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3700 Bottom 3709 T.D. 3709  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	oil & water	0	119	12 1/2"	18 1/2"	NONE
			3701	5 1/2"	3701	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
RUN 2" TUBINGS TO 1500' - CIRCULATED 60 SY CEMENT TO SURFACE USING 250# HULLS. PULLED TUBINGS OUT & REENTERED WITH ANOTHER 1 1/2" SX & SHUT IN AT 200#. CEMENTED 12 1/2" WITH 50 SY CEMENT & 50# HULLS.

Name of Plugging Contractor: Allied Cementing Inc. License No. \_\_\_\_\_  
 Address Box 31 Russell, Ks 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bowman Oil Company  
 STATE OF Kansas COUNTY OF Rooks, ss.  
Louis

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Louis D. Bowman  
 (Address) 805 Codell Rd - Codell, Ks 67663

SUBSCRIBED AND SWORN TO before me this 13TH day of SEPTEMBER, 1996

RECEIVED KANSAS CORP COMM  
 My Commission Expires: 7-17-2000  
Vesta J. Russell  
 Notary Public

USE ONLY ONE SIDE OF EACH FORM



**COPY**

**K.A.S. LIBRARY**

COMPANY BARNETT DRILLING COMPANY

SEC. 9 T. 9 R. 21W


FARM Clack NO. 2

LOC. NW SE SW

15-065-01361-00-00

TOTAL DEPTH 3709  
 COMM. 4-9-51 COMP. 4-30-51  
 SHOT OR TREATED  
 CONTRACTOR  
 ISSUED 6-19-51

COUNTY Graham



CASING  
 12 1/2" 119'  
 5" 3701'

ELEVATION 2188

PRODUCTION 12 1/2 bbls / 10% water

FIGURES INDICATE BOTTOM OF FORMATIONS

clay 30  
 sand 47  
 shale, shells 840  
 sand, shells 975  
 shale, shells 1150  
 sand 1200  
 shale, shells 1300  
 sand 1360  
 red rock 1450  
 shale, shells 1664  
 anhydrite 1712  
 shale 1800  
 shale, shells 2050  
 lime, shale, shells 2305  
 lime, shale 2435  
 lime 2555  
 shale, lime 3240  
 lime 3580  
 lime, shale 3680  
 lime 3702 RTD  
 lime 3709  
 Total Depth

Tops: K.B.  
 Heebner 3354  
 Lansing 3393  
 Base-Kansas city 3607  
 Arbuckle 3700

3700  
 2188  
 -----  
 1512

3393  
 2188  
 -----  
 1205

RECEIVED  
 KANSAS CORP COMM  
 1996 OCT -2 A 12: 08