


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-065-02449-00-00

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 28 Twp. 9 Rge. (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines C S/2 SW SE/4
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name Baldwin Well No. 1
Office Address 908 Palace Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Jan. 15, 19 55
Application for plugging filed Jan. 15, 19 "
Application for plugging approved " " 19 "
Plugging commenced " " 19 "
Plugging completed " " 19 "
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3943 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	195'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated hole with heavy Rotary mud and set cementing
plug at 190 ft. and 1/2 sack Hulls and 15 sacks cement.
Mudded hole to 40 ft., set cementing plug and 1/2 sack Hulls
and 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. L. C. Sponenberg, employee of contractor
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. C. Sponenberg*
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of January, 19 55

My commission expires February 13, 1956.

Rose Lacey
Notary Public.

PLUGGING
FILE SEC 28 T 9 R 2/4
BOOK PAGE 91 LINE 34

JAN 25 1955
CONSERVATION DIVISION
Wichita, Kansas

15-005-02449-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Herman Geo. Kaiser & Francis Oil & Gas, Inc.

SEC. 28 T. 9 R. 21W
LOC. C S/2 SW SE

FARM Baldwin NO. 1

COUNTY Graham

TOTAL DEPTH 3943


COMM. 1/4/55

COMP. 1/15/55

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED



CASING

20	10
15	8 195'
12	6
13	5

ELEVATION 2326 D.F.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay & Sand	70
Sand & Shale	115
Shale	980
Shale & Sand	1310
Sand	1540
Shale	1565
Shale & Shells	1785
Anhydrite	1835
Shale, Shells & Red Bed	2105
Shale, Shells & Salt	2295
Shale & Lime	2785
Shale & Sand, very soft	2820
Shale & Lime - Broken	2840
Shale & Lime	3584
Lime	3716
Lime - Cherty & Iron	3745
Lime & Shale	3869
Conglomerate & Shale	3899
Conglomerate & Chert	3937
Conglomerate	3943

FORMATION TOPS

HEEBNER	3523
TORONTO	3546
LANSING-K.C.	3564
BASE KANSAS AC.	3788
CONGLOMERATE	3855

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

By *C. P. Spurr*

STATE OF KANSAS }
 } SS:
COUNTY OF SEDGWICK }

Subscribed and sworn to before me, a notary public, in and for said County and State this 21st day of January, 1955.

Rose Lusey
Notary Public

My Commission expires February 13, 1956.

1-25-55

PLUGGING
FILE SEC 28 T. 9 R. 21W
BOOK PAGE 91 LINE 34