

15-065-01141-00-00

R

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 31 Twp. 9 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner Morgenstern & Specter, Inc.
Lease Name C. Smith "A" Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 12-11-64 19____
Plugging completed 12-12-64 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	211'	None
				5-1/2"	3881'	300'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3885', sanded hole to 3870' and dumped 5 sacks of cement @ 3870' with dump bailer. Mudded hole from 1370' to 600', set rock bridge to 590' and dumped 6 sacks of cement @ 590'. Pulled 5 1/2" casing and ran 3 1/2 yards of ready mix cement to cap well.

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1964

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

12-18-64

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/representative) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 1964

My commission expires May 20, 1968

Notary Public.


Company- WESTGATE-GREENLAND OIL CO.
 Farm- Smith "L" No. 1

SEC. 31 T. 9 R. 21W
 SW SW SE

15-065-01141-00-00

County Graham
 KANSAS

Total Depth. 3885 R.B.
 Comm. 1-8-52 Comp. 1-24-52
 Shot or Treated.
 Contractor. Jackson Drlg.
 Issued. 4-5-52



Elevation. 2310 D.F.

Production. 25 bbls. temp.

CASING:

8 5/8" 211' cem. w/150 sx.
 5 1/2" 3881' cem. w/100 sx.

Figures Indicate Bottom of Formations.

sand & soil	75
shale	185
shale & shells	211
sand & shale	300
shale & shells	900
sand	1090
shale & shells	1350
shale	1525
red bed & shells	1690
shale & shells	1780
anhyd., limo & sand	1815
shale & shells	1905
shale	2200
shale & shells	2260
limo & shale	2370
limo	2410
limo & shale	2620
limo	2630
limo & shale	2830
limo	2900
limo & shale	3020
limo	3075
limo & shale	3460
limo	3500
limo & shale	3534
limo	3760
shale	3773
shale & limo	3823
chert, shale & limo	3856
sand & shale	3882
arb. limo	3885
Total Depth R.B.	

"OWWO"
 CO: EARL M. KNIGHTON
 WELL: #1 SMITH
 CARD ISSUED: 5-5-79
 IP: P 15 BO + 100 BWPD
 ARB OH 3881-3883
 NEW INFO: RE-ENTERED EST 12-18-78, WSH DWN TO
 TD 3883, ARB OH, POP

Tops:	
Anhyd.	1780
McCabner	3494
Dodge	3515
Mansing	3532
Base L.C.	3758
Warmaton	3812
Simpson	3860
Arb.	3880

No Schlumberger, no tests made in Arb.
 C.O. to bottom, filled up 1600 oil in 2 hrs.
 2600' in 5 hrs., no wtr. bailed 10 bbls.
 in 2 hrs.

D.S.T. 3558-84, open 1/2 hr. rec. 480'
 salt wtr. BHP 1300#, blor press. 180#.
 3699-30 open 1/2 hr. rec 20' sl.
 oil & gas cut mud. No BHP
 3716-36, open 1/2 hr., rec 8' mud, BHP 300#.

RECEIVED
 STATE OF KANSAS

III 03 1985