

15-065-01141-0007

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME SMITH

WELL NUMBER 1

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 31 TWP. 9 RGE. 21 (X) of (W)

COUNTY Graham

Date Well Completed 3/14/52

Plugging Commenced 6/4/85

Plugging Completed 6/4/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hellar Drilling Company, Inc.

ADDRESS 711 Petroleum Bldg.
Wichita, Ks. 67202

PHONE#(316) 267-2845 OPERATORS LICENSE NO. 5015

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks.

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3880 Bottom 3883 T.D. 3883

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil & water	3880	83	8 5/8	211	none
				5 1/2	3881	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - feet to - feet each set.

Pump truck 3 sx hulls, 35 sx cement, 26 sx gel, 40 sx cement 4 sx gel, 25 sx cement,
Max Pr 1500# ST Pr 300#
Previous Info.: Well squeezed in Dakota when plugged 12/12/88. Squeezed w/200 sx from 298-346
when re-entered 12/17/78. Squeezed 500 sx cement 2730-3260 on 6/4/84.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. Inc. License No. NA

Address P O Box 31, Russell, Ks. 67665

STATE OF KANSAS COUNTY OF SEDGWICK

D. L. Hellar, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) President - D. L. Hellar
711 Petroleum Bldg.
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 19 85

My Commission Expires: March 25, 1988
Catherine Darcey
Notary Public -
Catherine Darcey



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas

COPY


15-065-01141-00-01

Company: WESTGATE-GREENLAND OIL CO.
 Farm: Smith "A" No. 1

SEC. 31 T. 9 R. 21W
 SW S. SE

Total Depth. 3885 R.B.
 Comm. 1-3-52 Comp. 1-24-52
 Shot or Treated.
 Contractor. Jackson Drlg.
 Issued. 4-5-52

County Graham
 KANSAS



Elevation. 2310 D.F.

Production. 25 bbls. temp.

CASING:

8 5/8" 211' cem. w/150 sx.
 5 1/2" 3881' cem. w/100 sx.

Figures Indicate Bottom of Formations.

sand & soil	75
shale	185
shale & shells	211
sand & shale	300
shale & shells	900
sand	1090
shale & shells	1350
shale	1525
red bed & shells	1690
shale & shells	1780
anhyd., lime & sand	1815
shale & shells	1905
shale	2200
shale & shells	2260
lime & shale	2370
lime	2410
lime & shale	2620
lime	2630
lime & shale	2830
lime	2900
lime & shale	3020
lime	3075
lime & shale	3460
lime	3500
lime & shale	3534
lime	3760
shale	3773
shale & lime	3823
chert, shale & lime	3856
sand & shale	3882
arb. lime	3885
Total Depth R.B.	

Tops:	
anhyd.	1780
Reebner	3494
Dodge	3515
Mansing	3532
Base L.C.	3758
Wormaton	3812
Simpson	3860
arb.	3880

No Schlumberger, no tests made in arb.
 C.O. to bottom, filled up 1600 oil in 2 hrs.
 2600' in 5 hrs., no wtr. bailed 10 bbls.
 in 2 hrs.

D.S.T. 3558-84, open 1/2 hr. rec. 480'
 salt wtr. BHP 1300#, blor press. 180#.
 3600-30 open 1/2 hr. rec 20' sl.
 oil & gas cut mud. No BHP
 3716-36, open 1/2 hr., rec 8' mud, BHP 800#.

RECEIVED
 STATE CORPORATION COMMISSION

NOV 30 1964

CONSERVATION DIVISION
 Wichita, Kansas