

15-065-00398-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County, Sec. 36 Twp. 9S Rge. 21 (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner K & E DRILLING, INC.
Lease Name RENNER Well No. #1
Office Address 1006 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed December 4, 19 54
Application for plugging filed December 4, 19 54
Application for plugging approved December 4, 19 54
Plugging commenced December 4 @ 8:00 a.m. 19 54
Plugging completed December 4 @ 12:00 noon 19 54
Reason for abandonment of well or producing formation
commercial quantity of oil not found

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3935' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	223'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled Hole with heavy mud from 3935' to 210'. Set wooden plug with 1/2 sack hulls and 15 sacks cement. Second plug at 40' and capped with 1/2 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E Drilling, Inc.
Address 1006 Central Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott, agent for (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
1006 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of December, 19 54

James Miller
Notary Public.



PLUGGING
FILE SEC 36 T 9 R 21 W
BOOK PAGE 82 LINE 26

RECEIVED
STATE CORPORATION COMMISSION
12-10-54

15-065-00398-00-00

K & E DRILLING, INC.
RENNER #1

NE NE SE 36-9S-21W
Graham County, Kansas

Comm: 11-23-54
Comp: 12-4-54
Total Depth: 3935'

Casing Cement
8 5/8" Set @ 223' 140 sacks

<u>FORMATION</u>	<u>DEPTH</u>
Clay	0 - 30
Sand & clay	30 - 60
Clay, shale & sand	60 - 190
Blue shale	190 - 223
Shale	223 - 925
Sand & shale	925 - 1020
Shale & shells	1020 - 1340
Sand	1340 - 1475
Red bed	1475 - 1810
Anhydrite	1810 - 1845
Shale & shells	1845 - 2144
Shale lime	2144 - 2400
Lime & shale	2400 - 3025
Lime	3025 - 3125
Lime & shale	3125 - 3555
Lime	3555 - 3580
Lime & shale	3580 - 3595
Lime, K.C.	3595 - 3630
Lime	3630 - 3825
Lime & shale	3825 - 3895
Lime & chert	3895 - 3903
Lime & shale	3903 - 3910
Chert- conglomerate	3910 - 3925
Lime- Arbuckle	3925 - 3935

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Dale Silcott

Subscribed and sworn to before me this 8th day of December, 1954.

My commission expires: 6-25-56

Francois Markler

Notary Public

PLUGGING
WELL NO. 36-9-21W
BOOK PAGE 12 LINE 28

12-10-54