

15-065-20058-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Graham SEC. 36 TWP. 9S RGE. 21W E/W
 Location as in quarters or footage from lines:
C N/2 NW SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner J.A. Allison
 Lease Name Lambert #1 Well No.
 Office Address Suite 305 300 W. Douglas Wichita, Ks. 67202-2975
 Character of Well (Completed as Oil, Gas or Dry Hole):
 Date Well Completed
 Application for plugging filed
 Plugging commenced 7-16-82
 Plugging completed 7-23-82
 Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
 Producing formation Depth to top bottom T.D. 3883'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	280'	None
				5-1/2"	3883'	2110'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set.

Ran 1 barrel of sand and 5 sacks cement and pushed bottom plug to 3650'. Shot casing
 @3100', 2986', 2871', 2754', 2654', 2530', 2317' and 2126'. Pulled atotal of 65 joints
 of 5-1/2" casing. Sun Oilwell Cementing plugged well with 5 sacks hulls, 25 sacks
 gel, 140 sacks 50/50 pos, 6% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Ks. 67524
 (address)
 AUG 09 1982
 CONSERVATION DIVISION
 Wichita, Kansas
 Notary Public.

SUBSCRIBED AND SWORN TO before me this 5th day of August 19 82



My Commission expires:

8-9-82

B & B DRILLING, INC.

548 Petroleum Building

Wichita, Kansas 67202

July 14, 1967

DRILLERS LOG

Re: #1 Lambert
C N/2 NW SW
Section 36-9S-21W
Graham County, Kansas

COMPANY: Allison & Black
CONTRACTOR: B & B Drilling Inc.
TOTAL DEPTH: 3883'
COMMENCED: July 3, 1967
COMPLETED: July 11, 1967

0	30	Soil & Clay	
30	90	Sand	
90	226	Shale	
226	321	Shale	
321	1350	Shale & Sand	
1350	1455	Sand & Shale	
1455	1768	Shale & Red Bed	
1768	1813	Anhydrite	
1813	2215	Shale & Lime	
2215	2440	Lime & Shale	
2440	2655	Lime & Shale	Heebner; 3508
2655	2880	Lime & Shale	Topeka; 3535
2880	3025	Lime & Shale	Kansas City; 3549
3025	3265	Lime & Shale	Cong; 3849
3265	3345	Lime & Shale	Arbuckle 3875
3345	3538	Lime & Shale	
3538	3597	Lime & Shale	
3597	3655	Lime DST # 1	
3655	3715	Lime DST # 2	
3715	3755	Lime	
3755	3780	Lime & Shale DST #3	
3780	3847	Lime	
3847	3875	Lime	
3875	3883	Arbuckle DST #4	
3883		Total Depth	Ran 5 1/2" casing w/125 sx

RECEIVED

STATE CORPORATION COMMISSION

JAN 26 1967

CONSERVATION DIVISION
Wichita Kansas

We certify the above and foregoing to be true and
Correct copy of the log on the #1 Lambert, located
in Graham County, Kansas

Bill Lalor President

Alma A. Musis Notary Public

Subscribed and sworn to before me this 14th
day of July, 1967
My commission expires May 31, 1970