

15-065-20083-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 36 Twp. 9 Rge. (E) 21 (W)  
Location as "NE/CNW/SW" or footage from lines SE NW SW  
Lease Owner Allison & Black  
Lease Name Lambert Well No. 2  
Office Address 1415 Wichita Plaza - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry  
Date well completed 9-12 19 67  
Application for plugging filed 9-12 19 67  
Application for plugging approved 9-12 19 67  
Plugging commenced 4:00 PM 9-12 19 67  
Plugging completed 6:00 P.M. 9-12 19 67  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production none 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3895 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Shale		0	220	8 5/8"	218	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole with 100 sacks Paz. & 6% Grt. Ran 1180' with pipe & cemented with 100 sacks. Ran 240' drill pipe & cemented with 25 sacks - 40' with 10 sacks hole plugged with pump truck at 6:00 pm

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1967

9-20-67

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 15 1967

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & B Drilling, Inc.  
Address 548 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Bill Lahar

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar  
548 Petroleum Building - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of September, 19 67



Alma G Reiser

Notary Public.

B & B DRILLING, INC.

548 Petroleum Building

Wichita, Kansas 67202

15-065-20083-00-00

September 14, 1967

DRILLERS' LOG

Re: #2 Lambert  
SE NW SW  
Section 36-9S-21W  
Graham County, Kansas

COMPANY: Allison & Balck  
CONTRACTOR: B & B Drilling, Inc.  
TOTAL DEPTH: 3895'  
COMMENCED: September 5, 1967  
COMPLETED: September 12, 1967

0	220	Sand & Shale
220	635	Shale
635	1120	Shale & Sand
1120	1175	Sand
1175	1265	Shale
1265	1425	Sand & Shale
1425	1458	Sand & Shale
1458	1771	Shale & Red Bed
1771	2362	Shale & Lime
2362	2645	Shale & Lime
2645	2748	Lime
2748	3005	Shale & Lime
3005	3155	Shale & Lime
3155	3350	Shale & Lime
3350	3500	Shale & Lime
3500	3557	Shale & Lime
3557	3643	Lime & Shale
3643	3686	Lime
3686	3735	Lime DST # 1
3735	3738	Lime
3738	3825	Lime
3825	3841	Lime
3841	3868	Lime & Shale
3868	3895	Lime Log
3895		T. D. D & A.

Heebner	3510'
Toronto	3534'
Lansing	3550'
B/K.C.	3770'
Colog.	3838'
Arbuckle	3880'

RECEIVED  
STATE CORPORATION COMMISSION

SEP 15 1967


9-15-67

CONSERVATION DIVISION  
Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the #2 Lambert, located in Graham County, Kansas

Bill Lohar President

Olma A. Neuse Notary Public



My commission expires  
May 31, 1970

Subscribed and sworn to before me this  
14th day of September, 1967