


15-065-21278-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County, Sec. 1 Twp. 9s Rge. 22W N/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SE SE SE  
Lease Owner Arrowhead Petroleum, Inc.  
Lease Name Buss Well No. 1  
Office Address Box 8287, Munger Station, Wichita, KS 67208  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Dry Hole  
Date Well completed 7-28-80 19  
Application for plugging filed 7-28-80 19  
Application for plugging approved 7-28-80 19  
Plugging commenced 7-28-80 19  
Plugging completed 7-28-80 19  
Reason for abandonment of well or producing formation

Dry Hole  
If a producing well is abandoned, date of last production  
N/A 19  
Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gil Baltazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3815  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand				8 5/8"	228'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

70 sx 800'  
20 sx 232'  
10 sx 40'  
5 sx RH  
50 - 50 PAZ 6% gel

RECEIVED  
STATE CORPORATION COMMISSION  
AUG - 4 1980  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Service Company


STATE OF Kansas COUNTY OF Sedgwick, ss.  
Paul A. Seymour, III (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul A. Seymour III  
Box 8287, Munger Station, Wichita, KS 67208  
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of August, 1980

Ruth M. Bassett  
Ruth M. Bassett Notary Public.

My commission expires May 30, 1983



15-065-21278-00-00

# BIG SPRINGS DRILLING, INC.

P.O. BOX 8287  
MUNGER STATION  
WICHITA, KANSAS 67208

SUITE 29 • 400 NORTH WOODLAWN • (316) 681-1732

August 1, 1980

## DRILLERS LOG

Re: Buss # 1  
SE SE SE  
Sec. 1-Twp 9s-Rq 22W  
Graham County, Kansas

OPERATOR: Arrowhead Petroleum, Inc.  
CONTRACTOR: Big Springs Drilling, Inc.  
COMMENCED: 7-23-80  
COMPLETED: 7-28-80

Surface pipe: Set 228' of 8 5/8" w/165 sx Common 2% gel 3% ccl

0	228	Sand & Clay
228	1736	Sand & Shale
1736	1776	Anhydrite
1776	3185	Shale and Shells
3185	3610	Shale & Lime
3610	3815	Lime
3815		RTD

RECEIVED  
STATE CORPORATION COMMISSION  
AUG - 4 - 1980  
CONSERVATION DIVISION  
Wichita, Kansas

We certify that the above and foregoing is a true and correct copy of the log on the # 1 Buss located in Graham County, Kansas.

BIG SPRINGS DRILLING, INC.

*Paul A. Seymour III*  
Paul A. Seymour, III

Subscribed and sworn to before me this 1st day of August, 1980.

*Ruth M. Bassett*  
Ruth M. Bassett Notary Public

My Commission Expires **RUTH M. BASSETT**  
STATE NOTARY PUBLIC  
Sedgewick County, Kansas  
May 30, 1983 My Appt. Exp. \_\_\_\_\_