


15-179-00182-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas



Locate well correctly on above Section Plat

Sheridan County, Sec. 21 Twp. 8S Rge. 26 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines NE NE SW
Lease Owner C-G Drilling Co. & N. Appleman Co.
Lease Name McClelland Well No. 1
Office Address 107 Rule Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 1 19 56
Application for plugging filed February 1 19 56
Application for plugging approved February 1 19 56
Plugging commenced February 2 19 56
Plugging completed February 2 19 56
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3837 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	354'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 340'.
Set plug. Put in 1/2 sack Hulls and 15 sacks of cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack Hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
G. F. Galloway
107 Rule Bldg.
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of February, 19 56
My commission expires May 20, 1959



Vicky Jacobs
Vicky Jacobs
Notary Public.
STATE COMMISSION

FEB 15 1956 2-13-56

PLUGGING
FILE SEC 21 T 8 R 26w
BOOK PAGE 37 LINE 7

CONSERVATION DIVISION
Wichita, Kansas

15-179-00182-00-00

CONTRACTOR'S WELL LOG

OPERATOR C-G DRILLING CO. & N. APPLEMAN CO. WELL NAME McCLELLAND #1

LOCATION NE NE SW Sec. 21-8S-26W RIG NO. 2

COUNTY SHERIDAN STATE KANSAS

COMMENCEMENT DATE JANUARY 22, 1956 COMPLETION DATE FEBRUARY 1, 1956

LOG OF WELL

Elevation 2423 rotary bushing.
All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	50	Surface Soil		
50	240	Sand-Shale		
240	3354	Shale		
354	955	Shale		
955	1130	Sand-Shale		
1130	1250	Shale-Red Bed		
1250	1640	Shale-Shells		
1640	2030	Red Bed		
2030	2048	Red Bed		
2048	2085	Anhydrite		
2085	2335	Shale-Shells		
2335	2465	Shale-Shells		
2465	2650	Shale-Shells	0° - 2500	
2650	2775	Shale-Shells	0° - 2750	
2775	2945	Shale-Shells		
2945	3005	Shale-Lime	0° - 3000	
3005	3100	Shale-Lime		
3100	3180	Lime		
3180	3250	Shale-Lime	0° - 3250	
3250	3365	Shale-Lime		
3365	3465	Shale-Lime		
3465	3525	Lime	0° - 3500	
3525	3570	Lime		
3570	3619	Shale-Lime		
3619	3638	Lime		DST 3631 - 38
3638	3710	Lime		
3710	3753	Lime	0° - 3750	DST 3722 - 45
3753	3837	Lime		

CASING LEFT IN HOLE AFTER COMPLETION


354' of 8-5/8" OD Surface Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway



Subscribed and sworn to before me this 6th day of February, 1956.

My commission expires:
May 20, 1959

Vicky Jacobs
Vicky Jacobs, Notary Public

2-13-56

PLUGGING
PAGE 37 LINE 1