


15-179-051930000

Q

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

County. Sec. 22 Twp. 8 Rge. 26 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner M.J. Bove
Lease Name Pratt Well No. 9
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 11-13 19 44
Application for plugging filed 6-12 19 68
Application for plugging approved 6-17 19 68
Plugging commenced June 25 19 68
Plugging completed June 28 19 68
Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production Not known 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation L-KC Depth to top 3610 Bottom 3812 Total Depth of Well 3840 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-Kansas City	Oil & Water	3656	3812	10 3/4"	277	None
				7"	3802	1281'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3840 feet to surface feet for each plug set.

Set bridge at 3500' put 10' of sand on bridge Dump 5 sacks of cement.
Pulled pipe from hole plug hole. Use 50-50 Pos. 6% Gel. Pump 130 Sk. from 1185' to 860', 17 Sx. 860' to 225', 25 Sx. from 225' to 175', 5 sx. 175 to 30', 10 sx. on top.
Well completed.

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.
Address P.O. Box 313 Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
E. T. Drube (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
754 E. Wichita Ave, Russell, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of July, 19 68

My commission expires January 5, 1969.
Ruth E Miller Notary Public.

15-179-05193-0000

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1968
CONSERVATION DIVISION
Wichita, Kansas

UNION OIL COMPANY OF CALIFORNIA

Wichita, Kansas

PRATT NO. 9
CNW NW SE Sec. 22-8S-26W
Sheridan County, Kansas

Casing Record:
10-3/4" 277' with 250 sax cement
7" 3802' " 225 " "

Commenced: February 7, 1944

Completed:

Elevation: 2457

<u>LOG</u>			<u>TOPS</u>	
<u>From</u>	<u>To</u>	<u>Formation</u>		
0	280	Surface	Anhydrite	2080
280	1025	Shale	Topeka	3420
1025	1435	Shale & shells	Kansas City	3610
1435	1500	Lime, shells & shale		
1500	1690	Shale & shells	Porous zones:	
1690	1865	Sand	1st zone	3656-3661
1865	2075	Shale & shells	2nd zone	3669-3674
2075	2080	Lime	3rd zone	3700-3706
2080	2120	Anhydrite	4th zone	3750-3754
2120	2640	Shale & shells	5th zone	3786-3790
2640	2700	Lime	6th zone	3804-3812
2700	2733	Lime & shale		
2733	2751	Sandy shale		
2751	2810	Lime		
2810	2945	Lime & shale		
2945	3015	Lime		
3015	3028	Shale & lime		
3028	3054	Lime		
3054	3080	Shale & lime		
3080	3145	Lime		
3145	3265	Broken lime		
3265	3345	Lime & shale		
3345	3381	Lime		
3381	3393	Shale & lime shells		
3393	3840	Lime T.D.		

Wichita, Kansas, Dated Feb. 23, 1944

By: W. W. Heathman
Manager of Kansas Operations