


STATE OF KANSAS
CORPORATION COMMISSION

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 23 Twp. 8 Rge. (E) 26 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$ SW $\frac{1}{4}$ SE $\frac{1}{4}$
Lease Owner Michigan Oil Company (Musgrove Pet. Corp. - Operator)
Lease Name Pratt Well No. 6
Office Address 407 K.F.H. Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 19...
Application for plugging filed October 12 19 50
Application for plugging approved October 14 19 50
Plugging commenced November 6 19 50
Plugging completed November 11 19 50
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production None 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3769 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"	3748'	1812'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Mudded hole to 200'. Put in rock bridge. Ran 20 sacks cement. Mudded hole from top of cement at 152' to 25'. Put in rock bridge. Ran 10 sacks cement. Filled hole to top.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Musgrove Petroleum Corporation
Address 407 K.F.H. Building
Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling

(Address)

SUBSCRIBED AND SWORN to before me this 20th day of November, 19 50.

My Commission Expires December 5, 1951

RECEIVED
STATE CORPORATION COMMISSION
Notary Public. *Madeline J. ...*



PLUGGING
FILE SEC 22 T 8 R
BOOK PAGE 35 LINE 18

NOV 20 1950
CONSERVATION DIVISION
Wichita, Kansas

C
O
P
Y

C
O
P
Y

UNION OIL COMPANY OF CALIFORNIA
Wichita, Kansas

Pratt No. 6
CNW SW SE Sec. 23-8S-26W
Sheridan County, Kansas

Casing Record:
10-3/4" surface casing cemented at
202' with 200 sacks cement

Elevation 2420' Est.

<u>LOG</u>			<u>TOPS</u>	
<u>From</u>	<u>To</u>	<u>Formation</u>		
0	204	Surface	Topeka	3355
204	775	Shale	Heebner	3555
775	1650	Shale & shells	Kansas City	3600
1650	1830	Sand		
1830	2065	Shale & shells		
2065	2095	Anhydrite	Porous zones:	
2095	2225	Shale	1st zone	3632-3638
2225	2400	Shale & shells	2nd zone	3644-3650
2400	2550	Broken line	3rd zone	3676-3680
2550	3085	Lime	4th zone	3725-3730
3085	3130	Shale	5th zone	3763-3767
3130	3230	Lime		
3230	3265	Shale		
3265	3350	Lime & shale		
3350	3375	Shale		
3375	3405	Lime		
3405	3435	Cherty lime		
3435	3460	Lime		
3460	3495	Shale		
3495	3515	Lime		
3515	3525	Shale & streaks sand		
3525	3555	Lime		
3555	3557	Shale		
3557	3575	Lime		
3575	3580	Brown dense & flaky lime		
3580	3590	Green shale		
3590	3600	Gray lime		
3600	3625	Cherty lime		
3625	3632	Shale, red		
3632	3638	Lime, porous, oil stains		
3638	3644	Lime		
3644	3650	Lime, porous, oil stains		
3650	3665	Lime		
3665	3676	Shale		
3676	3680	Lime, porous, oil stains		
3680	3718	Lime		
3718	3725	Shale		
3725	3730	Lime, porous, oil stains		
3736	3737	Black shale		
3737	3740	Brown lime		
3740	3747	Red shale		
3747	3751	Gray lime		
3751	3760	Gray shale		
3760	3765	Porous lime, oil stains		
3765	3769	Lime T.D.		

Wichita, Kans., November 23, 1943

By /s/ W. W. Heathman
Manager of Kansas Operations

STATE CORP. 10-14-1950

FILED 23. 8. 1943

BOOK PAGE 35-118-18