


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sheridan County. Sec. 23 Twp. 8 Rge. 26 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NW NW SW
Lease Owner K.R. M. Petroleum Corporation
Lease Name Pratt #7 Well No. _____
Office Address Little River, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/13/76 _____ 19____
Plugging completed 9/28/76 _____ 19____
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
depleted.

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes _____

Name of Conservation Agent who supervised plugging of this well Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3865
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				12 $\frac{1}{2}$ "	262	none
				7"	3843	1229'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pushed plug to 3400' and ran 5 sacks cement. Shot pipe at 2713', 2504', 2328',
2017', 1806', 1620', 1500', 1408', 1316', 1225', pulled 40 joints. Pumped 5 sacks
hulls, 15 sacks gel and 170 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

OCT 08 1976
10-8-1976
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of October, 1976

Margaret Melcher
Notary Public.

My commission expires



MAR 11 1944

15-179-05201-00-01

ORIGINAL

23-8-26W
C 7W NW SW

UNION OIL COMPANY OF CALIFORNIA

WICHITA, KANSAS

Bot. 317 B.

PRATT NO. 7

~~CNW~~ NW SW Sec. 23-8S-26W
Sheridan County, Kansas

Casing Record:

10-3/4" set at 262' -- 260 sacks cement
7" " " 3843' -- 200 " "

Commenced: November 23, 1943
Completed: December 17, 1943

Elevation: 2496'

LOG

<u>From</u>	<u>To</u>	<u>Formation</u>
0	265	Surface
265	360	Shale
360	815	Shale & shells
815	1150	Shale & sand
1150	1200	Sand
1200	1415	Shale & shells
1415	1635	Sand & shale
1635	1730	Shale & shells
1730	1900	Sand
1900	2015	Broken lime
2015	2123	Shale & shells
2123	2160	Anhydrite
2160	2415	Shale & shells
2415	3315	Lime
3315	3395	Shale
3395	3565	Lime & shale
3565	3865	Lime T.D.

TOPS

Anhydrite	2123'
Topeka	3437'
Kansas City	3650'

Porous zones:

1st zone	3697-3702'
2nd zone	3709-3713'
3rd zone	3734-3743'
4th zone	3780-3796'
5th zone	3824-3830'
6th zone	3844-3852'

Wichita, Kansas, March 1st, 1944

By W. W. Heathman
Manager of Kansas Operations

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1976
8-31-1976
CONSERVATION DIVISION
Wichita, Kansas