

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-179-20,604 -00-01

LEASE NAME Pratt

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 3

330 Ft. from S Section Line

 Ft. from E Section Line

SEC. 23 1450' FWL, NE/4
TWP. 8s RGE. 26 (E) or (W)

COUNTY Sheridan

LEASE OPERATOR Northern Lights Oil Co.

ADDRESS P.O. Box 164, Andover, KS 67002

PHONE# (316) 733-1515 OPERATORS LICENSE NO. 5474

Character of Well LKC Injection Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed

Plugging Commenced 7-14-93

Plugging Completed 7-14-93

The plugging proposal was approved on (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4150

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	203'	None
				4 1/2	4116'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug job only. Pumped 4 1/2" casing with 200 sks cement w/400# hulls. Maximum pressure 1500#. Shut in at 1500#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PLUGGING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Northern Lights Oil Co.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 19th day of July

Jane Herberg
 Notary Public
 STATE CORPORATION COMMISSION
 RECEIVED
 JUL 20 1993
 CONSERVATION DIVISION
 Wichita, Kansas
 Revised 05-88

My Commission Expires:


15-179-20604-00-01

MURFIN DRILLING CO
617 UNION CENTER BLDG
WICHITA, KS 67202

1541

#3 PRATT

23-8-26W
330' FSL &
1450' FWL, NE/4

CONTR MURFIN DRG CO CTY SHERIDAN

GEOL ROGER WELTY FIELD STUDLEY

2438 KB CM 6/15/81 CARD ISSUED 12/23/81

LKC 3640-3773 OA

+	+
+	+
+	+
+	+

API 15-179-20,604 +368

LOG	TOPS	DEPTH	DATUM
ANH		2074	+368
B ANH		2108	+330
TOP		3367	-929
HEEB		3576	-1138
TOR		3597	-1159
LANS		3612	-1174
B KC		3824	-1386
CHER SH		4011	-1573
MISS		4116	-1678
PSTD		4088	-1650
RTD		4150	-1712
LTD		4151	-1713

8-5/8" 203/160sx, 4 1/2" 4116/250sx

DST (1) 3625-3674(LKC)/45-45-45-45, REC 60'ocm (10% o, 5% w, 85% m), 60'ocmw, (3% o, 22% w, 75% m), 60'slocmw (1% o, 38% w, 61% m), 180'mw, SIP 1053-1022#, FP 130/240#

DST (2) 3672-3692(LKC)/45-45-45-45, REC 15'M, SIP 684-653#, FP 40/51#

DST (3) 3712-3743(LKC)/30-60-30-60, REC 180'msw, 753'VSLC BLACKISH W, SIP 940-940#, FP 153/428#

NOTE: ORIGINAL LOC WAS 330' FSL & 1450' FWL, SW/4 (OVER)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

this well is now LKC injective well

This well is 2 staged no pipe pulling just plug

MURFIN DRILLING CO.

#3 PRATT

23-8-26W
330' FSL &
1450' FWL, NE/4

DST (4) 3749-3785(LKC)/30-60-30-60, REC 80' M W/SPTS O, SIP 1125-1104#, FP 102/120#

DST (5) 3783-3808(LKC)/30-60-30-60, REC 90' M W/SPTS O, SIP 581-756#, FP 102/102#

MICT - CO, PF 24/3733-36, 16/3640-42, 16/3654-58 & 8/3771-73, AC PF'S W/ 1000 GAL, TSTD, POP, P G BOPD & 163 BWP, 11/6/81

RECEIVED
STATE AND RELATION COMMISSION

JUN 23 1993
6-23-1993
CONSERVATION DIVISION
Wichita, Kansas