

15-179-05209-00-01

WELL PLUGGING RECORD


STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

Sheridan County, Sec. 26 Twp. 8 Rge. (E) 26 (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW/4 NE/4 NW/4 Lease Owner Michigan Oil Company (Musgrove Petroleum Corp-Operator) Lease Name Schlemeyer (Coltrin) Well No. 1 Office Address 407 K.F.H. Building, Wichita, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed 19 Application for plugging filed October 12 19 50 Application for plugging approved October 14 19 50 Plugging commenced October 28 19 50 Plugging completed November 5 19 50 Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Producing formation Depth to top Bottom Total Depth of Well 3750 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 5-1/2", 3745', 1522'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 240'. Put in 5' rock bridge. Ran 20 sacks cement. Mudded to 30'. Put in rock bridge. Run 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Musgrove Petroleum Corporation Address 407 K.F.H. Building Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss. GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November 19 50.

RECEIVED STATE CORPORATION COMMISSION Notary Public.



December 5, 1951

22-7877-s

4-49-10M

NOV 20 1950

PLUGGING FILE SEC 26 T 8 R 26 W BOOK PAGE 35 LINE 7

CONSERVATION DIVISION Wichita, Kansas

11-20-1950

C
O
P
Y

15-179-65209-00-01

C
O
P
YUNION OIL COMPANY OF CALIFORNIALOG OF SCHLEMEYER WELL #1NW¹/₄ NE¹/₄ NW¹/₄ SECTION 26-8-26, SHERIDAN COUNTY, KANSAS

<u>Formation</u>	<u>From</u>	<u>To.</u>	<u>Remarks</u>
Surface Clay	0	100	
Surface clay & shells	100	250	Set 10 3/4" surface pipe @ 248', cemented with 225 sacks
Shale	250	475	
Lime Stone	475	540	
Shale	540	870	
Shale & shells	870	1750	
Sand and shells	1750	1900	
Shale	1900	1970	
Shale & red rock	1970	2110	
Anhydrite	2110	2155	
Shale & shells	2155	2425	
Red shale & shells	2425	2505	
Lime	2505	2550	
Lime & shells	2550	2655	
Broken lime	2655	2670	
Lime & shale	2670	2695	
Shale & shells	2695	2740	
Lime	2740	2800	
Shale	2800	2848	
Shale & shells	2848	2953	
Lime	2953	3205	S.L.M. Correction 3000 to 2998
Shale & shells	3205	3295	
Broken lime & shale	3295	3325	
Lime	3325	3868	Circulated 1 1/2 hrs. @ 3840', and 1 1/4 hrs. @ 3852'.
Lime & shale	3868	3880	Circulated 1 1/4 hrs. @ 3880'.
Total Depth		3880	Dry and abandoned.

TOPS

Base of Ft. Hays	580'
Anhydrite	2112'
Ft. Riley	2663'
Topeka	3434'
Kansas City	3648'

Wichita, Kansas November 18, 1944

By _____
Manager of Kansas Operations