

15-179-00008-0000

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

Sheridan County, Sec. 7 Twp. 8 Rge. (E) 26 (W)

NORTH

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE/4 NE/4 NE/4

Lease Owner The Derby Oil Company

Lease Name Flagler Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 11 19 44

Application for plugging filed July 13 19 44

Application for plugging approved July 15 19 44

Plugging commenced July 13 19 44

Plugging completed July 13 19 44

Reason for abandonment of well or producing formation Not Productive

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, phone to State Agent

Name of Conservation Agent who supervised plugging of this well Eldon R. Petty

Producing formation None Depth to top Bottom Total Depth of Well 4880 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	306	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4880' to 280' - Heavy Rotary mud
 280' to 212' - Wood Plug - 15 sacks of cement
 212' to 38' - Heavy Rotary mud
 38' to 6' - Wood Plug, and cement
 6' to Surface - Earth

PLUGGING
 FILE SEC 7-8 R26W
 BOOK PAGE 124 LINE 38

STATE CORPORATION COMMISSION
 AUG 11 1944
 WICHITA, KANSAS

8-11-44

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Derby Oil Company

Address Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

S. E. Banks (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. E. Banks

Wichita, Kansas
(Address)

My commission expires July 31, 1947 2nd day of August 19 44

[Signature]
Notary Public.



15-179-00008-00-00

THE DERBY OIL COMPANY

Record of Well No. 1
 Location: NE/c
 Contractor: Crow Drlg. Co.
 Drilling Commenced: 6-19-44
 Elevation: 2576

Farm: Flagler
 Sec. 7 Twp. 8 Rge. 26W
 County: Sheridan
 State: Kansas
 Drilling Completed: 7-11-44

CASING RECORD

size	feet	weight	kind
8 5/8"	306'		140 sax Halliburton bulk cement

Formation	Bottom	Formation	Bottom
Surface Sand	0- 45	Lime Broken	3694
Shells & Shale	88	Lime & Shale	3768
Sand & Gravel	156	Circ. 1 1/2 hr. in Lime	3780
Shale	320	Circ. 1 1/2 Hr. in Lime	3800
Shale & Shells	840	Lime	3864
Shale & Lime Shells	885	Circ. 1 1/2 hr. in Lime	3879
Anhydrite & Shale	910	Circ.	3895
Shale & Shells	1087	Lime	3939
Shale & Sand Streaks	1240	Lime & Shale	3990
Shale & Shells	1420	Lime	4020
Shale & Sand	1440	Sandy Lime	4047
Shale & Shells	1615	Shale & Lime	4058
Sandy Lime	1655	Shale	4115
Shale & Lime Shells	1737	Shale & Lime	4189
Shale & Shells	2225	Shale	4248
Anhydrite Shale	2260	Lime	4277
Anhydrite	2270	Shale & Lime	4434
Shale & Shells	2698	Sand & Shale	4473
Shale	2770	Sandy Lime	4483
Lime	2806	Sand	4504
Shale	2861	Lime & Shale	4532
Lime & Shale	2913	Sand & Shale	4730
Lime	2980	Lime	4814
Lime & Shale	3204	Cherty Lime	4855
Lime	3250	Lime	4880
Shale	3290		
Lime & Shale	3542		
Lime Broken	3574		
Lime	3637		

GEOLOGICAL SURVEY

Tops:

Anhydrite	2224'
Topeka	3552'
Lansing	3774'
BKC	4032'
Miss. L.	4749'
Arbuckle	4812'
Total Depth	4880'

PLUGGING
 FILE 7-8-26W
 BOOK PAGE 124 LINE 30

Good Por. no sho 4860'

Ran Schlumberger log from 730 to 4876'-
 no shows.

