

15-179-20028-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 10 Twp. 8S Rge. 26 (X) West (W)
Location as "NE/CNW/SW" or footage from lines S/2 SW SW
Lease Owner Joe Katz Oil Account
Lease Name Twell Well No. 1
Office Address 7751 Carondelet Avenue, Clayton, Missouri 63105
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 9 19 67
Application for plugging filed July 9 19 67
Application for plugging approved July 9 19 67
Plugging commenced July 9, 6:00 a.m. 19 67
Plugging completed July 9, 7:00 a.m. 19 67
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3845 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT*
	Surface	0	230'	7"	X	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 780', 60 sacks cement thru drill pipe.
Filled hole with heavy mud to 230', 15 sacks cement, filled hole
with heavy mud to 40', 15 sacks cement, 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1967

7-20-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address Box 129, Sterling, Kansas 67579
Conservation Division
Wichita, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) *F. A. Wuellner*
F. A. Wuellner, Secretary
Box 129, Sterling, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 19th day of July, 19 67

BERNARD LAUDERMILK, Notary Public
My commission expires Commission Expires January 22, 1970

Bernard Laudermilk
Bernard Laudermilk, Notary Public.



15-79-20028-00-00

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- TWELL #1
LOCATED: S/2 SW SW Section 10-8S-26W, Sheridan County, Kansas

OWNER: Joe Katz Oil Account
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 2, 1967
COMPLETED: July 9, 1967

ROTARY TOTAL DEPTH: 3845'

LOG

0 - 150	Clay & Sand
150 - 830	Shale
830 - 2110	Shale & Sand
2110 - 2155	Anhydrite
2155 - 2470	Shale
2470 - 3133	Shale & Lime
3133 - 3845	Lime T.D.

CASING RECORD

Run 7 joints 7" 20# used seamless casing. 221.70' pipe set at 230' K.B., cemented with 200 sacks 50 - 50 Pozmix with 2% gel. Plug was down at 8:15 a.m. by Sun Cementing Company.

Plugged as follows: filled hole with heavy mud to 780', 60 sacks cement thru drill pipe. Filled hole with heavy mud to 230', 15 sacks cement; filled hole with heavy mud to 40', 15 sacks cement. 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSIONER

JUL 20 1967 7-20-67

CONSERVATION DIVISION
Wichita, Kansas