


15-179-00204-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Sheridan County. Sec. 12 Twp. 8S Rge. 26W (E) (W)

Location as "NE/CNW%SW%" or footage from lines. NW NW SE  
Lease Owner Don Pratt Oil Operator  
Lease Name Pratt Well No. 1  
Office Address Box 656, Hays, Kansas 67601  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-21-64 19  
Application for plugging filed 12-21-64 19  
Application for plugging approved 12-21-64 19  
Plugging commenced 12-21-64 19  
Plugging completed 12-21-64 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4000 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. One row contains: 8 5/8", 183', none.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 540' Plug 20 sacks cement  
Mud to 180' Plug 20 sacks cement through drill pipe  
Mud to 40' 1/2 sack hulls 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

DEC 30 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc. 12-30-64  
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 1964

My commission expires April 1, 1967

Wanda [Signature] Notary Public.

15-179-00204-00-00

DRILLER'S LOG

COMPANY: Don Pratt Oil Operator  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: PRATT #1  
 LOCATION: NW NW SE Sec. 12-8S-26W  
 SHERIDAN COUNTY, KANSAS  
 COMMENCED: 12-14-64  
 COMPLETED: 12-21-64

0	186	Shale
186	785	Shale & Sand
785	1745	Shale
1745	2045	Red Rock Shale
2045	2179	Shale & Sand
2179	2214	Anhydrite
2214	2365	Shale
2365	2620	Shale & Lime
2620	3240	Lime & Shale
3240	3810	Lime
3810	3819	Lime with Shale Streaks
3819	4000	Lime
	<u>4000</u>	<u>Rotary Total Depth - D. &amp; A.</u>

Set 8 5/8" new surface casing @ 183' with 150 sacks HA5

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Pratt #1 well, located NW NW SE of Section 12, Township 8 South, Range 26 West, Sheridan County, Kansas, as reflected by the files of Leben Drilling, Inc.

*Leslie Kite*

Leslie Kite

**RECEIVED**  
STATE CORPORATION COMMISSION


DEC 30 1964

CONSERVATION DIVISION  
Wichita, Kansas

12-20-64

STATE OF KANSAS )  
 COUNTY OF BARTON ) SS

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 29th day of December, 1964.



*Ulanda Nichols*

Ulanda Nichols

My Commission Expires  
April 1, 1967