


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plot

Sheridan County, Sec. 17 Twp. 8 Rge. 26 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SW/4
Lease Owner Dreiling Oil, Inc.
Lease Name Kysar Well No. 2
Office Address Rt. #2, Victoria, KS 67671
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 6-22 1973
Application for plugging filed 9-23 1974
Application for plugging approved 9-24 1974
Plugging commenced 11-16 1974
Plugging completed 11-16 1974
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production March 1974
Was permission obtained from the Conservation Division or its agents before plugging was commenced? W.L. Nichols, P.O. Box 157, Morland, KS 67650

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3,875 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	166'	0
Casing				4 1/2"	3,874'	1,769'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with 5 sacks Hulls, 30 sacks Gel, 100 sacks cement.
Pumping pressure, 200#, shut in pressure 50#.

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1974
11-19-1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Dreiling Oil, Inc.
Address Rt. #2, Victoria, KS 67671

STATE OF KANSAS COUNTY OF ELLIS, ss.
I, Joseph A. Hess, Sec. Treas. of Drlg. Contr. (Employer or owner or lessee or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph A. Hess
JOSEPH A. HESS, Hays, KS 67601
(Address)

Subscribed and sworn to before me this 18th day of November, 1974
September 13, 1976
Cecilia Basgall
Notary Public.



DREILING OIL, INC.

Victoria, Kansas 67671

Dreiling Oil, Inc.		WELL LOG		
Rt. #2				
Company	Victoria, Kansas 67671	Sec. 17	Twp. 8	Rng. 26
Farm	Kysar No. 2	Location	C SW/4	
Total Depth	3,875'	County	Sheridan	
Comm.	6-4-73	Comp.	6-22-73	Elevation: 2441' K. B.
Contractor	Dreiling Oil, Inc.			2438 D. F.
	Rt. #2			2436 G. R.
	Victoria, Kansas 67671			

Casing Record	Cement Record	Production:
166' - 5 5/8"	165 sacks cement	
3,874' - 4 1/2"	cemented w/20 bbl. fresh water	
	& 200 gal. B.J. Flush & 50 sks	
	Poz Mix 27% Cel & 12% Gilsnite per sk	
	175 sks common 12% salt	
	Figures Indicate Bottom of Formations	

0'	35'	Sand
35'	65'	Gray Shale
65'	166'	Blue Shale
166'	1315'	Shale
1315'	1704'	Shale & Gyp
1704'	1873'	Sand
1873'	1930'	Red Bed & Shale
1930'	2088'	Shale
2088'	2123'	Anhydrite
2123'	2925'	Shale
2925'	3217'	Shale & Lime
3218'	3600'	Shale
3600'	3875'	Lime
3875'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1974
9-24-1974
CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Joe Hess, Secretary Treasurer of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Kysar #2.

Joe Hess

JOE HESS

Subscribed and sworn to before me this 20th day of June, 1973.



Cecilia Basgall

Cecilia Basgall Notary Public

My commission expires: September 13, 1976.