

15-179-20476-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 9-14-77
LEASE NAME Kysar
WELL NUMBER 5
SPOT LOCATION C SE SW
SEC. 17 TWP. 8 RGE. 26 (E) or (W)
COUNTY Sheridan
Date Well Completed 9-14-77
Plugging Commenced 3-27-85
Plugging Completed 3-27-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Dreiling Oil, Inc.
ADDRESS Box 1000, Victoria, Kansas 67671
PHONE # (913) 735-2204 OPERATORS LICENSE NO. 5145

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist #6, 1014 Cody, Hays, KS 67601

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation KC Depth to top _____ bottom _____ T.D. 3844'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface				8 5/8"	178	0'
Casing				4 1/2"	3842'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged with 200 sks 50/50Poz Mix, 6% Gel, 3% CC, 20 sks gel, 5 sks hulls, Max. pressure 300 P.S.I. shut in Pressure 1000 P.S.I.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Dreiling Oil, Inc. License No. 730
Address Box 1000, Victoria, KS 67671

STATE OF KANSAS COUNTY OF ELLIS, ss.

Bill Draper (employee of operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill Draper
(Address) Box 1000, Victoria, KS 67671

SUBSCRIBED AND SWORN TO before me this 28th day of March, 19 85



My Commission expires:

Cecilia Basgall
Notary Public

DREILING OIL, INC.

Victoria, Kansas 67671

WELL LOG

Company	Dreiling Oil, Inc. Rt. #1 Victoria, KS 67671	Sec. 17	Twp. 8	Rng. 26
Farm	Kysar No. 5	Location	C SE SW	
Total Depth	3,844'	County	Sheridan	
Comm.	9-8-77	Comp.	9-14-77	Elevation: 2444
Contractor	Dreiling Oil, Inc. Rt. #1 Victoria, KS 67671			K. B.
			2441	D. F.
			2439	G. R.

Casing Record	Cement Record	Production:
178' - 8 5/8"	150 sacks cement	
3,842' - 4 1/2"	cemented w/150 sacks	
	common	

Figures Indicate Bottom of Formations

0'	40'	Sand
40'	1525'	Shale
1525'	1600'	Shale & Gyp
1600'	2087'	Shale
2087'	2122'	Anhydrite
2122'	2999'	Shale
2999'	3648'	Shale & Lime
3648'	3691'	Lime
3691'	3770'	Lime & Shale
3770'	3844'	Lime
3844'	T.D.	

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Kysar #5.

Joseph A. Hess

 JOSEPH A. HESS

Subscribed and sworn to before me this 26th day of September, 1977.

Cecilia Basgall

 Cecilia Basgall Notary Public

NOTARY PUBLIC
 STATE OF KANSAS

My appointment expires: November 17, 1980.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 08 1985
 3-8-1985
 CONSERVATION DIVISION
 Wichita, Kansas