

15-179-20252-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sheridan County, Sec. 18 Twp. 8 Rge. 26 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines C NE SE 150' South

Lease Owner Herman George Kaiser

Lease Name F. Karnes Well No. 1

Office Address 909 Palace Building, Tulsa, Oklahoma 74109

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-31 1970

Application for plugging filed 5-31 1970

Application for plugging approved 5-31 1970

Plugging commenced 5-31 1970

Plugging completed 5-31 1970

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	196'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug was set @ 1200' with 70 sacks cement

2nd plug was set @ 215' with 20 sacks cement

3rd plug was set @ 40' with 10 sacks cement

RECEIVED
JUN 2 1970
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.

Address Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.


(Signature) Leo F. Dreiling

LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of June, 19 70

My commission expires September, 1970

Joseph A. Hess
JOSEPH A. HESS
Notary Public.



L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

Company Herman George Kaiser
 909 Palace Building
 Tulsa, Oklahoma 74109

Farm F. Karnes No. 1

Total Depth 3852'

Comm. 5-25-70 Comp. 5-31-70

Contractor L. J. Dreiling & Sons, Inc.
 Victoria, Kansas 67671
 Casing Record
 196' - 8 5/8"

Sec. 18 Twp. 8 Rng. 26

Location C NE SE 150' South

County Sheridan

Elevation: 2478' K. B.
 2475' D. F.
 2473' G. R.
 Production: D & A

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 2 1970
 CONSERVATION DIVISION
 Wichita, Kansas
 6-2-1970

Cement Record
 150 sacks cement

Figures Indicate Bottom of Formations


0'	45'	Surface Soil - Sand
45'	230'	Shale
230'	413'	Shale
413'	1580'	Shale & Sand
1580'	1590'	Shale
1590'	1640'	Shale - Dyp.
1640'	1750'	Shale
1750'	1915'	Sand
1915'	2126'	Shale
2126'	2145'	Anhy.
2145'	2161'	Anhy.
2161'	2400'	Shale & Schells
2400'	2680'	Shale & Lime
2680'	2880'	Lime & Shale
2880'	3105'	Lime - Shale
3105'	3290'	Lime & Shale
3290'	3410'	Lime & Shale
3410'	3575'	Lime - Shale
3575'	3670'	Lime & Shale
3670'	3705'	Lime
3705'	3745'	Lime
3745'	3815'	Lime
3815'	3852'	Lime
3852'	T.D.	

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your F. Karnes #1.

Leo F. Dreiling
 LEO F. DREILING

Joseph A. Hess
 JOSEPH A. HESS - NOTARY PUBLIC



Subscribed and sworn to before me this 1st day of June, 1970.

My commission expires: September 19, 1970