

15-179-20038-06-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

SHERIDAN County, Sec. 19 Twp. 8 Rge. 26 (X) W (W)

Location as "NE/CNW/SE" or footage from lines SE SE SE

Lease Owner DANE G HANSEN TR

Lease Name TAYLOR #1 Well No.

Office Address LOGAN, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed AUG. 25, 1967 19

Application for plugging filed AUG. 25, 1967 19

Application for plugging approved AUG. 25, 1967 19

Plugging commenced AUG. 25, 1967 19

Plugging completed AUG. 25, 1967 19

Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS, MORELAND, KANSAS

Producing formation Depth to top Bottom Total Depth of Well 3930 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

8-31-67

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	201.39'	NONE

RECEIVED  
AUG 31 1967  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH HEAVY MUD TO 1740'. SET PLUG. PUT IN 100 SACKS CEMENT. FILLED WITH HEAVY MUD TO 190'. SET PLUG. PUT IN 1 1/2 SACKS HULLS AND 20 SACKS CEMENT. FILLED WITH HEAVY MUD UP TO 40'. SET PLUG. FILLED TO TOP WITH 1/2 SACKS HULLS AND 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G DRILLING CO.  
Address 107 RULE BUILDING, WICHITA, KANSAS 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss.  
JAY H. GALLOWAY (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H Galloway  
JAY H GALLOWAY 107 RULE BUILDING  
(Address)

Subscribed and sworn to before me this 29th day of AUGUST, 19 67



Phyllis McJimsey  
PHYLLIS McJIMSEY Notary Public.

15-179-20038-00-00

29

WELL LOG

OPERATOR: DANE G HANSEN TR

WELL NAME: TAYLOR #1 LOCATION: SE SE SE 19-8-26W

COUNTY: SHERIDAN STATE: KANSAS

WELL COMMENCED: 8/18/67 WELL COMPLETED: 8/25/67

ELEVATION: 2544 KB TOTAL DEPTH: 3930'

PRODUCTION: D & A RIG NO: 1

CASING - 8-5/8": 10 jts 201.39' 28# USED CASING W/150 SX CEMENT +  
5-1/2": 2 SX CA. CL.

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
201	855	SHALE	1/4° 500'	
855	1635	SHALE & SAND	1/4° 1000'	DST #1 3718-3760
1635	1740	SHALE	1/4° 1500'	DST #2 3839-3885
1740	1940	SAND	1/4° 1500'	
1940	2183	SHALE & RED BED	1 1/2° 2000'	
2183	2222	ANHYDRITE	1 1/4° 2500'	
2222	2410	SHALE & SHELLS	1 1/4° 3362'	
2410	2570	SHALE		
2570	3260	SHALE & LIME		
3260	3362	LIME		
3362	3685	LIME & SHALE		
3685	3930	LIME		

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 31 1967  
8-31-67  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS  
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway  
JAY H. GALLOWAY

SUBSCRIBED AND SWORN TO, BEFORE ME, This 29th day of AUGUST, 1967.



Phyllis McJimsey  
Phyllis McJimsey ---Notary Public