

15-179-20073-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Taylor #2

WELL NUMBER _____

SPOT LOCATION SE SW

SEC. 19 TWP. 8 RGE. 26 (#) or (W)

COUNTY Sheridan

Date Well Completed _____

Plugging Commenced 11/30/84

Plugging Completed 12/4/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Dane G. Hansen Trust

ADDRESS Box 187, Logan, Ks. 67646

PHONE # (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3861'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	187'	none
				4 1/2"	3859'	895'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom plug - Pushed plug to 3045' & ran sand & 4 sacks cement. Shot pipe at 2519', 2026', 1728', 1509', 1222', 1012', & 895'. Pulled 30 joints of pipe. Plugged well with 4 hulls, 40 gel, & 170 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

12-19-84
RECEIVED

STATE OF Kansas COUNTY OF Rice, ss. STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) of DEC 19 1984

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 17th day of December, 1984



Irene Hoover
Notary Public

My Commission expires: _____

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

15-179-20673-00-00

WELL LOG

Company **D. C. Hansen Trust** Sec. **19** Twp. **8** Rng. **26**
Box 187
Logan, Kansas 67646
 Farm **Taylor** No. **2** Location **3E-SW**
 Total Depth **3860'** County **Sheridan**
 Comm. **2-7-68** Comp. **2-14-68** Elevation: **2481' K.B.**
2478' D.F.
 Contractor **L. J. Drilling & Sons, Inc.** **2474' G.R.**
Route 2
Victoria, Kansas 67671

Casing Record Cement Record Production:
187' 8 5/8" **125 sacks cement**
3859' 4 1/2" **150 sacks Salt**
 Saturated cement

Figures Indicate Bottom of Formations


0'	60'	Sand
60'	187'	Shale
187'	500'	Sand & Shale
500'	1020'	Shale
1020'	1236'	Shale & Sand
1236'	1575'	Shale & Cyp
1575'	1712'	Shale
1712'	1867'	Sand
1867'	2098'	Shale & Redbed
2098'	2133'	Anhy.
2133'	2235'	Shale
2235'	2330'	Shale
2330'	2420'	Shale & Lime
2420'	2760'	Shale & Lime
2760'	3010'	Lime
3010'	3130'	Lime & Shale
3130'	3420'	Lime & Shale
3420'	3580'	Lime
3580'	3615'	Lime
3615'	3665'	Lime
3665'	3670'	Lime
3670'	3720'	Lime
3720'	3760'	Lime
3760'	3780'	Lime
3780'	3820'	Lime
3820'	3860'	Lime & Shale
3860'	T.D.	

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Drilling, of the L. J. Drilling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from you Taylor #2.

Leo F. Drilling
 LEO F. DREILING

Subscribed and sworn to before me this 15th day of February 1968.



Joseph A. Hegg
 JOSEPH A. HEGG NOTARY PUBLIC

My commission expires: September 19, 1970