


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-179-60191-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Sheridan County. Sec. 20 Twp. 8 Rge. 26 (X) (W)  
Location as "NE/CNWxSWx" or footage from lines NW NW SW  
Lease Owner Woodman & Iannitti Drilling Co. & Harfred Oil Company  
Lease Name Pfiefer Well No. 1  
Office Address P. O. Box 387, Hoisington, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-5 1957  
Application for plugging filed 10-5 1957  
Application for plugging approved 10-5 1957  
Plugging commenced 10-5 1957  
Plugging completed 10-5 1957  
Reason for abandonment of well or producing formation Dry.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3940 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	148'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Jet pits filled with heavy mud. Bottom plug at 500 with 20 sacks of cement. Second plug at 140 with 15 sacks cement. Top plug at 40' with 10 sacks cement and 1/2 sack hulls.

RECEIVED  
OCT 9 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Woodman & Iannitti Drilling Company  
Address P. O. Box 387, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
K. T. Woodman (employee of owner) (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman  
717 Union National Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of October, 1957

Mildred E. Lick  
Mildred E. Lick, Notary Public.

My commission expires March 15, 1961



PLUGGING  
FILE SEC 20 T. 8 R. 26 W  
BOOK PAGE 52 LI. E. 15

13-179-00191-00-00

DRILLING LOG

Company: Woodman & Iannitti and Harfred Oil Co.  
 Lease: #1 PFIEFER  
 Location: NW NW SW Sec. 20-8-26W  
 Sheridan County, Kansas  
 Contractor: Woodman & Iannitti Drilling Company  
 P. O. Box 387, Hoisington, Kansas  
 Date Commenced: 9/26/57  
 Date Completed: 10/5/57  
 Total Depth: 3940'  
 Casing: 8 5/8" set at 148' with 120 sacks of cement.

Figures Indicate the Bottom of Formation

0-50	Shale	3015	Shale - Lime
120	Sand & Shale	3100	Lime
148	Blue Shale	3185	Lime
480	Shale	3260	Lime
1200	Shale - Sand	3335	Lime
1400	Sand - Shale	3407	Lime
1720	Shale - Lime	3500	Lime - Shale
1775	Red Rock	3590	Lime
2165	Redbed & Shale	3670	Lime
2204	Anhydrite	3730	Lime
2315	Shale & Shells	3790	Lime
2350	Shale & Shells	3795	Lime
2515	Shale - Lime	3850	Lime
2705	Shale - Lime	3900	Lime
2870	Shale & Lime	3940	Lime

GEOLOGICAL TOPS

Elevation	2510	RB
Anhydrite	2165	345
Heebner	3658	-1146
Toronto	3679	-1169
Lansing	3698	-1188
Base/K.C.	3912	-1402
Total Depth	3940	-1430

I certify the above to be a true and correct copy of the Driller's log and geological tops to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

By: K. T. Woodman  
K. T. WOODMAN

**PLUGGING**  
 FILE SEC. 20. 18. 26W  
 BOOK PAGE 52. LINE 15

8747  
 OCT 9 1957  
 DIVISION  
 10-9-57