

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-179-20179-00-00

LEASE NAME Jerome

WELL NUMBER 3

       Ft. from S Section Line

       Ft. from E Section Line

SEC. 35 TWP. 8 RGE. 27 (E) or (W)

COUNTY Sheridan

Date Well Completed 1

Plugging Commenced 6-26-91

Plugging Completed 6-26-91

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-26-91 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filed?        If not, is well log attached?       

Producing Formation        Depth to Top        Bottom        T.D.       

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	251	8 5/8		None
	Casing	0	4000	5 1/2		None

7/8/91  
 JUL 08 1991

CONSERVATION DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from        feet to        feet each set.  
 Perf. 2290 2 shots 1440 2 shots Run tubing to 3344.66'. Spot 50 sk. 65/35 pos with 8% gel. Pull 34 jts. to 2229.77'. Spot 50 sk. 65/35 pos with 8% gel. Pull 34 joints to 1114.88. Circulate cement to surface with 50 sk. 65/35 pos with 8% gel. Hook to 5 1/2 casing. Pump 130 sks. 65/35 pos with 8% gel. Mix. 250# pressure Shut in 150#. Hook to surface and mix 120 sks. 65/35 with 8% gel. Mix pressure 100#. Shut in pressure 50#.

Name of Plugging Contractor Berexco License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks 67601

NOTARY PUBLIC-State of Kansas  
 ROSEMARY SMITH  
 My Appt. Exp. 5-1-1995

SUBSCRIBED AND SWORN TO before me this 5 day of July, 19 91

Rosemary Smith  
 Notary Public

My Commission Expires: 5-1-1995