


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-179-20192-00-00
WELL PLUGGING RECORD

SHERIDAN County, Sec. 35 Twp. 9S Rge. 27 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW NE NW.
Lease Owner OKMAR OIL CO.
Lease Name JEROME #5 Well No. _____
Office Address 1130 WICHITA PLAZA, WICHITA, KANSAS 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MARCH 14, 1969 19____
Application for plugging filed MARCH 14, 1969 19____
Application for plugging approved MARCH 14, 1969 19____
Plugging commenced MARCH 14, 1969 19____
Plugging completed MARCH 14, 1969 19____
Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3970 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258.78'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED WITH HEAVY MUD TO 1325'. SET PLUG. PUT IN 100 SACKS CEMENT. FILLED WITH HEAVY MUD TO 275'. SET PLUG. PUT IN 20 SACKS CEMENT. FILLED WITH HEAVY MUD UP TO 40'. SET PLUG. PUT IN 10 SACKS CEMENT AND 1 SACK OF HULLS FILLED TO TOP.

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1969
CONSERVATION DIVISION
Wichita, Kansas


5/23/69

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING CO.
Address 1107 UNION NATIONAL BLDG., WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. JAY H GALLOWAY (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H Galloway
JAY H GALLOWAY 1107 UNION NATIONAL BLDG.
(Address) WICHITA, KANSAS

Sworn to before me this 14 day of MARCH, 19 69



Phyllis Buchanan
PHYLIS BUCHANAN Notary Public.

My commission expires DEC. 7, 1971

15-179-20192-00-00

WELL LOG

OPERATOR: OKMAR OIL CO.

WELL NAME: JEROME #5

LOCATION: SW NE NW SEC 35-⁸S-27W

COUNTY: SHERIDAN

STATE: KANSAS

WELL COMMENCED: MARCH 5, 1969

WELL COMPLETED: MARCH 14, 1969

ELEVATION: 2643 KB

TOTAL DEPTH: 3970'

PRODUCTION: DRY & ABANDONED

RIG NO: 1

CASING - 8-5/8": 13 jts. 258.78' w/180 SACKS QUICKSET

5-1/2": _____

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	258	SAND & SHALE	3/4° 500'	DST #1 3802-3831'
258	1477	SHALE	3/4° 1000'	DST #2 3830-3885'
1477	1695	SHALE & SAND	3/4° 1500'	DST #3 3829-3846'
1695	2247	SHALE	1/2° 2000'	straddle
2247	2286	ANHYDRITE	3/4° 2500'	DST #4 3904-3925'
2286	2540	SHALE & SHELLS	1/2° 3160'	DST #5 3925-3970'
2540	3777	LIME & SHALE	1° 3745'	
3777	3885	LIME		

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1969
CONSERVATION DIVISION
Wichita, Kansas

4/23/69

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway
Jay H. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This 14th day of MARCH, 1969

MY COMM. EXP. DEC. 7, 1971

Phyllis Buchanan
PHYLLIS BUCHANAN - NOTARY PUBLIC

