

15-179-00035-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Sheridan

County. Sec. 7 Twp. 8 Rge. (E) 28(W)

Location as "NE/CNWxSWx" or footage from lines 330'S 345'W North/4 Corner

Lease Owner Cities Service Oil Co.

Lease Name James #B KCC ZAP Well No. 1

Office Address Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 2/25/54 19

Application for plugging filed 2/25/54 19

Application for plugging approved 2/25/54 19

Plugging commenced 2/26/54 19

Plugging completed 2/26/54 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Arbuckle Depth to top 4673' Bottom Total Depth of Well 4688 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	280'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 270', set Halliburton plug, 1/2 sx. hulls, 15 sx. cement, mud to 40', set Halliburton plug, 1/2 sx. hulls and 10 sx. cement to surface.


Name of Plugging Contractor Bill Hay Drilling Co.
Address Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss. James Porter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Porter
Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 2nd day of March, 1954

My commission expires 3-17-1955
W. E. Smith Notary Public.



PLUGGING
FILE NO. 218-28W
BOOK PAGE 10 LINE 3

3-12-54

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm James #2 KCC ZAP
 Location 330' South and 345' West of N/4 Cor. Sec. 7 T. 8 R. 28W
 Elevation 2775 (2772 Gr.) County Sheridan State Kansas
 Drlg. Comm. February 8, 1954 Contractor Bill May Drilling Company
 Drlg. Comp. February 25, 1954 Acid None
 T. D. 4688' Initial Prod. None - Dry Hole; P. & A. 2-25-54.

CASING RECORD:

8-5/8" 280' cas. 215 cc cement.

FORMATION RECORD:

clay & sand	0-70
sand & shale	185
sand	230
clay	248
shale	580
shale, shells & sand	1270
shale & sand	1620
streaks sand & shale	1740
shale & shells	2100
shale, shells & red bed	2425
shale & shells	2472
anhydrite	2507
shale, red bed & shells	2715
shale & red bed	2800
shale & shells	3018
shale & lime	3150
shale & shells	3285
lime	3339
shale & shells	3414
shale	3440
shale & shells	3670
lime & shale	3903
lime	4145
lime & streaks shale	4205
lime & shale	4247
lime & streaks shale	4288
shale & lime	4485
lime	4557
lime & chert	4567
lime & streaks shale	4591
cherty lime	4620
lime	4688 T. D.

Anhydrite	2472'
Topeka	3680'
Hobner	3898'
Dodge	3919'
Lanning	3937'
Base Kansas City	4177'
Mississippi	4486'
Viola	4624'
Simpson	4670'
Artuckle	4673'
Penetration	15'
Total Depth	4688'

Drill stem test 3920-33, open 1 hr., recovered 5' mud; B. H. P. 1120#/30 mins.

Drill stem test 4113-45, open 1 hr., recovered 12' mud; B. H. P. 960#/30 mins.

SLOPE TESTS (SPRING SUN):

450'	1/2°
1000'	1/2°
1500'	1/2°
2000'	1/2°
2500'	3/4°
3050'	1/4°
3540'	1/4°
4500'	1/2°

7-7/8" rotary hole.

PLUGGING
 FILE SEC 7 T 8 R 28W
 BOOK PAGE 16 LINE 3

3-12-54