

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sheridan County, Sec. 23 Twp. 8 Rge. 28W (E) (W)

Location as "NE/CNW/SW" or footage from lines Approx. SW SW NW

Lease Owner Chief Drilling Co., Inc.

Lease Name Campbell Well No. #1

Office Address Box 797, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-12-69 19

Application for plugging filed 7-12-69 19

Application for plugging approved 7-12-69 19


Plugging commenced 7-12-69 19

Plugging completed 7-12-69 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3535 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	280'	8 5/8"	200 sacks cement	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 1400' w/100 sacks cement
Plugged through drill pipe @ 300' w/20 sacks cement
Plugged through drill pipe @ 40' w/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1969
CONSERVATION DIVISION
Wichita, Kansas

7-15-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ~~W. L. Nichols~~

Address ~~Merland, Kansas~~

STATE OF KANSAS, COUNTY OF BARTON, ss.
Jim Robinson (employee of owner) or ~~(owner or operator)~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
Box 797, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 1969



March 24, 1972 Clydene Williams Notary Public.

15-179-20216-00-00

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas 67530

Campbell #1
Approx. SW SW NW
Sec. 23-8S-28W
Sheridan County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 7-8-69
Completed: 7-12-69

Casing Record: 272' 8 5/8" set @ 280'
w/200 sacks cement

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface clay & sand	0	40	2639 Gr.
Shale & sand streaks	40	281	2642 D.F.
Shale & sand	281	1000	2644 K.B.
Shale, shell, & sand	1000	1660	
Shale & shells	1600	2342	<u>TOPS</u>
Anhydrite	2342	2376	Anhydrite 2342 + 302
Shall & shells	2376	2712	
Shale & lime	2712	3535	<u>LOG TOPS</u>
Total depth	3535		Anhydrite 2341 + 303
			Howard 3453 - 809
			Total depth 3535 - 891

STATE OF KANSAS, COUNTY OF BARTON) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled 2200' FN 440' FW of Section 23-8S-28W, Sheridan County, Kansas, to the best of my knowledge and belief.


CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 14th day of July, 1969.

Clydene Williams
Clydene Williams, Notary Public

My commission Expires:
March 24, 1972



7-15-69
RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1969
CONSERVATION DIVISION
Wichita, Kansas