


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Sheridan County. Sec. 26 Twp. 8-S Rge. 28 (E) (W)
Location as "NE/CNW/SW" or footage from lines C S/2 SE SE
Lease Owner Dean & Clark, Inc.
Lease Name Schaffer Well No. 1
Office Address 416 Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed March 9, 1968
Application for plugging filed March 29, 1968
Application for plugging approved March 9, 1968
Plugging commenced March 9, 1968
Plugging completed March 9, 1968
Reason for abandonment of well or producing formation completed as a dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Box 157, Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole from 20 feet below Base of Dakota at 1780 feet to 20 feet above Dakota at 1520 feet, cemented with 100 sacks 50/50 Pozmix. At base of surface set wood plug, cemented with 25 sks. 50/50 Pozmix. Set wood plug at 40 feet, cemented with 10 sks. Pozmix. Job completed at 11:15 P.M. 3-9-68.


RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Dean & Clark, Inc. 5-24-68
Address 416 Union Center Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jay C. Clark (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay C. Clark
416 Union Center Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of March, 1968.



August 30, 1969

Phyllis Gillen
Phyllis Gillen, Notary Public.

15-179-20078-00-00

DRILLERS LOG

COMPANY:
CONTRACTOR:
LEASE NAME:
LOCATION:

ELEVATION:
SURFACE CASING:
COMMENCED:
COMPLETED:
ROTARY TOTAL DEPTH:

Dean & Clark, Inc.
Company tools
Schaffer No. 1
C S/2 SE SE, Section 26-8S-28W
Sheridan County, Kansas
2702' K.B. 2699' D.F. 2697' G.L.
6 Jts. (248') 8-5/8"
February 28, 1968
March 9, 1968
4101 feet

FORMATION

DEPTH

Surface Soil-Sand-Shale	249	Spudded 12-1/4" hole at 10:00 P.M. 2-29-68.
Shale	2245	Drilled surface hole to 249 feet.
Shale-Red Bed	2336	Set 8-5/8" surface casing (6 Jts.) at 248'.
Anhydrite	2372	Cemented with 180 sacks common Sunset Cement.
Shale	2414	Cement circulated. Plug down at 3:00 P.M.
Shale-Lime	2891	2-29-68.
Lime-Shale	2988	
Shale	3075	No DST's taken.
Shale-Lime	3245	
Shale	3390	Ran Great Guns Radiation-Guard Electric Log
Shale-Lime	3436	
Lime	4101	Plugged well. Job completed at 11:15 P.M.
RTD	4101	March 9, 1968.

LOG TOPS

DEPTH

DATUM

Anhydrite	2340	+ 362
Tarkio	3514	- 812
Topeka	3606	- 904
Heebner	3821	-1119
Toronto	3846	-1144
Lansing	3860	-1158
Base Kansas City	4090	-1388
Log Total Depth	4102	-1400

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1968
CONSERVATION DIVISION
Wichita, Kansas

5-24-68

STATE OF KANSAS)
) ss:
COUNTY OF SEDGWICK)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

Jay C. Clark
Jay C. Clark

Subscribed and sworn to before me this 29th day of March, 1968.

Phyllis Gillen
Phyllis Gillen, Notary Public

My commission expires: August 30, 1969.

