


15-179-20106-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 22 Twp. 8S Rge. (E) 29(W)
Location as "NE/CNW%SW%" or footage from lines NW NW NE
Lease Owner Imperial Oil Co.
Lease Name Selbe Well No. 1
Office Address 780 Fourth National Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 29 19 68
Application for plugging filed May 29 19 68
Application for plugging approved May 29 19 68
Plugging commenced May 29 19 68
Plugging completed May 29 19 68
Reason for abandonment of well or producing formation No commercial
shows of oil and/or gas were encountered.
If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2570 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface casing at	243 ft.		8 5/8"		Not pulled.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 2570 feet to _____ feet for each plug set.

Set first plug at 1525 feet with 100 sacks cement.
Set second plug at 275 feet with 25 sacks cement.
Set third plug at 40 feet with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1968
CONSERVATION DIVISION
Wichita, Kansas
6-7-68

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil Company
Address 780 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
William A. Sladek (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL COMPANY

(Signature) William A. Sladek
William A. Sladek
780 Fourth National Bldg., Wichita, Ks.
(Address)

Subscribed and sworn to before me this 6th day of June, 19 68
Mary J. Brown
Mary J. Brown Notary Public.
My commission expires March 3, 1970



15-179-20106-00-00

DRILLER'S LOG

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas

Selbe No. 1
NW NW NE Sec. 22-8S-29W
Sheridan County, Kansas

Total Depth: 2570 feet

Elevation: 2817 K.B.

Commenced: 5-25-68

Completed: 5-29-68
Dry Hole

Contractor: Imperial Oil Company, Rig #2

Casing Record: Set 8 5/8 inch surface casing at 243 feet with
200 sacks cement.

Figures indicate bottom of formations:

243' Clay-sand
925' Shale-shells
1790' Shale-sand
2468' Shale-shells
2570' Anhydrite
2570' Rotary Total Depth

Electric Log Tops:

Top Anhydrite 2498 (+319)
Base Anhydrite 2534 (+283)
Total Depth 2570 (+247)

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By William A. Sladek
William A. Sladek

Subscribed and sworn to before me this 6th day of June, 1968.

Mary J. Brown
Mary J. Brown, Notary Public

My commission expires:
March 3, 1970

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1968
CONSERVATION DIVISION
Wichita, Kansas

15-179-20106-00-00

GEOLOGICAL REPORT

NO. 1 SELBE
NW NW NE Sec. 22-8S-29W
Sheridan County, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1968
CONSERVATION DIVISION
Wichita, Kansas

GEOLOGICAL REPORT

15-179-20106-00-00

Company: Imperial Oil Company
Farm: #1 Selbe
Contractor: Imperial Oil Co., Rig #2
Pool: Wildcat
Rotary Total Depth: 2570 ft.
Rotary Completed: May 28, 1968

Sheridan County, Kansas
440' from West Line and
440' from North Line of NE/4
Sec. 22-8S-29W
Elevation: 2817 K.B.

Geological Data:

Five foot drilling time was kept from 2400' to Rotary Total Depth.
(Electric log information: A Great Guns Gamma Ray Log was run from
Rotary Total Depth to 2570 feet.)

Formation Tops

Electric Log Tops


Top Anhydrite
Base Anhydrite
Total Depth

2498 (+319)
2534 (+283)
2570 (+247)

Porosity and Shows of Oil

This test ran approximately 30 feet low structurally on the Base of
the Anhydrite to wells in the area; therefore, it was recommended
this test well be plugged and abandoned at a Rotary Total Depth of
2570 feet.

IMPERIAL OIL COMPANY


Charley V. Shank
Geologist on Well

CVS:jl

DRILLING TIME LOG
NO. 1 SELBE
440' from West Line and
440' from North Line of NE/4
Section 22-8S-29W
Sheridan County, Kansas

Depth	Minutes	Remarks
-------	---------	---------

5' Intervals

2400-50	5-10-1	
2400-50	5-7-7-8-6/9-6-7-7-8	
2500	9-11-5-7-13/14-18-13-19-15	
2500-35	24-24-26-27-28/30-11-	

Drilling time was kept to only 2535 ft.

Rotary Total Depth 2570 ft.