

15-179-20027-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 14 Twp. 8S Rge. (E) 28 (W)
Location as "NE/CNWxSWx" or footage from lines C SE SE
Lease Owner Pickrell Drilling Company
Lease Name Campbell, "I" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 13, 1967
Application for plugging filed July 13, 1967
Application for plugging approved July 13, 1967
Plugging commenced July 13, 1967
Plugging completed July 13, 1967
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Box 157, Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	249'	None

8-17-67
RECEIVED
AUG 17 1967
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 1750'. Set plug. Cemented with 100 sacks cement.

Heavy mud to 205'. Set plug. Cemented with 20 sacks cement.

Heavy mud to 40'. Set plug. Cemented with 10 sacks cement

to bottom of cellar. Plugged rat hole with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts (owner or operator) of the above-described

sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 4th Nat'l Bank Bldg., Wichita, Ks. 67202
(Address)

Sworn to before me this 11th day of August, 1967.

L. M. Whiting
L. M. Whiting Notary Public.

My commission expires May 10, 1970



ROTARY DRILLING LOG

15-179-20027-00-00

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 6-30-67

Rotary Drilling Completed 7-13-67

LOCATION: Campbell "I" No. 1
C SE SE Section 14-8S-28W
Sheridan County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (12 jts.) 8 5/8" surface casing set at 249' and cemented with 160 sacks cement. Circ. Complete at 7:15 PM, June 30, 1967. No oil string was run. D. & A., plugged July 13, 1967.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

80	Post Rock & Shale	C. F. S.
1630	Shale & Shells	<u>3505</u>
1830	Sand	3525
1890	Shale & Shells	3545
2015	Shale, Shells & Red Beds	3580
2150	Sand	3610
2338	Shale, Shells & Red Beds	3715
2373	Anhydrite	3840
2600	Shale & Shells	3864
4410	Lime & Shale	3890
4450	Mississippian, RTD	3910
		4002
		4286
		4310
		4450

RECEIVED
STATE CONSERVATION COMMISSION
AUG 17 1967
8-17-67
CONSERVATION DIVISION
WICHITA, KANSAS

Slope Tests

2500
3000
3500
4000

S. L. M.

Strap	3336.72
Board	3369.10
Difference	32.38 long

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.


PICKRELL DRILLING COMPANY
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 11th day of August, 1967, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



L. M. Whiting
Notary Public

My commission expires: May 10, 1970