


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 26 Twp. 8 Rge. 26W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner DONALD C. SLAWSON
Lease Name Senger 'A' Well No. 1
Office Address 408 One Twenty Building - Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-14-1965
Application for plugging filed 7-14-1965
Application for plugging approved 7-14-1965
Plugging commenced 7-14-1965
Plugging completed 7-14-1965
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols - Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3956 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 550', set plug, 1/4 sack of hulls, 18 sacks of cement
Mud to 240', set plug, 1/4 sack of hulls, 20 sacks of cement
Mud to 40', set plug, 1/4 sack of hulls, 10 sacks of cement
2 sacks of cement in the rat hole

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1965

07-21-1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Slawson Drilling Company, Inc.
Address 408 One Twenty Building - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
DONALD C. SLAWSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

408 One Twenty Building - Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of July, 1965

Ella Priess

Ella Priess Notary Public.



15-179-30003-00-00

WELL LOG

Company: DONALD C. SLAWSON
 408 One Twenty Building
 Wichita, Kansas 67202

Farm: Senger 'A' #1
 C SW SW, Section 26-8-26W
 Sheridan County, Kansas

Total Depth: 3956' Elev. 2551 K.B.

Commenced: July 6, 1965
 Completed: July 14, 1965

Contractor: Slawson Drilling Company, Inc.

Casing: 8 5/8 @ 249' with 210 sacks of cement

0-249	Surface clay
249-1635	Shale
1635-2179	Shale & Shells
2179-2214	Anhydrite
2214-2520	Shale
2520-2750	Shale & Shells
2750-2855	Shale & Lime
2855-2960	Lime
2960-3425	Lime & Shale
3425-3564	Shale & Lime
3564-3703	Lime
3703-3721	Toronto
3721-3772	Lansing Kansas City
3821-3944	Lime
3944-3956	Sand
3956	Total Depth

RECEIVED
STATE CORPORATION COMMISSION


JUL 21 1965
07-21-1965
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, Donald C. Slawson, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Senger 'A' #1 well.


DONALD C. SLAWSON

Subscribed and sworn to before me this 20th day of July, 1965.


Ella Priess, Notary Public

