


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Sheridan County, Sec 22 Twp 8 Rgc (E) 26 (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner F & M Oil Co., Inc.

Lease Name Pratt Estate Well No. 1

Office Address 603 Union Center Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed December 8, 19 71

Application for plugging filed December 8, 19 71

Application for plugging approved December 8, 19 71

Plugging commenced December 8, 7:00 a.m. 19 71

Plugging completed December 8, 9:00 a.m. 19 71

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3860 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	259	8 5/8"	259	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

100 sacks through drill pipe @ 1150'  
25 sacks @ 275'  
10 sacks @ 40' plugged by Allied

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 2 1972  
CONSERVATION DIVISION  
Wichita, Kansas

3-2-1972

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert Jones  
Address 830 Sutton Place Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Eugene A. Falkowski (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Eugene A. Falkowski

(Address)

SUBSCRIBED AND SWORN to before me this 1st day of March, 19 72.

My commission expires July 27, 1975.

Wilma Riller, Notary Public.



GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

PRATT EST. #1  
SW SW NW, Section 27-8S-26W  
Sheridan County, Kansas

Commenced: November 29, 1971  
Completed: December 8, 1971

OPERATOR: F & M OIL CO.

Depth From	To	Formation	Remarks
0	40	Sand	Ran 12 jts. of used 28# 8 5/8" csg.
40	263	Shale and Sand	Set @ 259' w/180 sks common w/2% Gel
263	330	Shale	3% CC.
330	2076	Shale and sand	P.D. @ 10 PM 11/29/71
2076	2115	Anhydrite	Cement Circ.
2115	2175	Shale and lime strks	Job by Allied
2175	2902	Shale and shells	
2902	3695	Shale and lime	
3695	3860	Lime and shale	
3860	TD		Dry and Abandoned

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 2 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
3-2-1972

I, James S. Sutton II certify this is a correct copy of the Drillers' Log for the well drilled in the SW SW NW, Section 27-8S-26W, Sheridan County, Kansas, to the best of my knowledge and belief.

*James S. Sutton II*  
James S. Sutton II

STATE OF KANSAS )  
                                  ) SS  
COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 9th day of December, 1971, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.



*Marjorie Hall*  
Marjorie Hall, Notary Public