

STATE OF KANSAS
STATE CORPORATION COMMISSION
J. S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20,622-00-0

LEASE NAME Robben 'P'

WELL NUMBER 4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 27 TWP. 8 RGE. 26 (E) or (W)

COUNTY Sheridan

Date Well Completed

Plugging Commenced 6-4-96

Plugging Completed 6-5-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RitchiesExploration, Inc.

ADDRESS 125 N. Market, Ste 1000 --Wichita, Ks. 67202

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Carl Goodrow (KCC-District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3988'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	187'	none
				5 1/2"	3982'	1387'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 3695' and 5 sacks cement. Shot well at 2100', at 1700' and 1387'. Pulled 5-1/2" casing up to 1275' pumped 125 sacks cement with 300# hulls. Pulled up to 250' circulated to surface with 90 sacks cement. Pulled casing, topped off with 10 sacks cement. 60/40 10% gel. Plugging complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc. -- Wichita, Ks.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 13th day of June, 19 96

Irene Herzberg
Notary Public

CONSERVATION DIVISION
WICHITA, KS

My Commission Expires:



RECEIVED
KANSAS CORPORATION COMMISSION
6-17-1996
JUN 17 1996