


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Sheridan County. Sec. 1 Twp. 8 Rge. 27W (E) (W)

Location as "NE/CNWxSWx" or footage from lines NE NE SE  
Lease Owner Imperial Oil of Kansas, Inc.  
Lease Name Karnes Well No. 1  
Office Address 903 Union National Bank Bldg. Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 28, 19 55  
Application for plugging filed July 28, 19 55  
Application for plugging approved July 28, 19 55  
Plugging commenced July 28, 19 55  
Plugging completed July 28, 19 55  
Reason for abandonment of well or producing formation no shows of oil

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well S. S. Greider  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4641 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	285'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set #1 plug at 275' w/15 sacks cement. Filled hole with rotary mud to 40'. Set #2 plug w/10 sacks cement.


**RECEIVED**  
STATE CORPORATION COMMISSION  
AUG 4 X 1955  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Imperial Oil of Kansas, Inc. 8-4-55  
Address 903 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By Raymond L. Bacon V-P  
903 Union National Bank Building  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 19 1955



Francis E. Basham  
Notary Public.

**PLUGGING**  
FLK SEC 1 T 8 R 27W  
BOOK PAGE 139 LINE 16

15-179-05169-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
903 Union National Bank Bldg.  
Wichita 2, Kansas

Karnes #1  
NE NE SE Sec. 1-8-27W  
Sheridan County, Kansas

Total Depth: 4641'

Elevation: 2584' R.B.  
Production: D & A

Commenced: 7-12-55 Completed: 7-28-55

Contractor: Imperial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 285' W/200 sacks cement.

Figures indicate bottom of formations:

Surface Clay and Sand	40'			
Sand, Clay and Shale	285'		<u>TOPS</u>	
Clay and Shells	915'	Anhydrite	2232'	(-352)
Shale and Shells	1770'	Heebner	3737'	(-1153)
Dakota Sand	2015'	Toronto	3760'	(-1176)
Shale and Shells	2232'	Lansing	3776'	(-1192)
Anhydrite (hard)	2270'	Base Kansas City	4004'	(-1420)
Shale and Shells	2290'	Conglomerate	4331'	(-1747)
Shale and Lime	3830'	Mississippi Chert	4412'	(-1828)
Lime	4105'	Viola	4533'	(-1949)
Lime and Shale	4155'	Arbuckle	4625'	(-2041)
Lime	4641'	Rotary Total Depth	4641'	
Total Depth	4641'			

**RECEIVED**  
STATE CORPORATION COMMISSION  
AUG 4 X 1955  
CONSERVATION DIVISION  
Wichita, Kansas  
8-4-55

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Ray L. Bacon  
Vice President

Subscribed and sworn to before me this 3rd day of August, 1955.

Frances E. Barkan  
Notary Public

My Commission Expires:  
April 18, 1959

**PLUGGING**  
FLK SEC 1 T 8 R 27W  
BOOK PAGE 139 LINE 16