


15-179-05170-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 7 Twp. 8S Rge. 27 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SE SE SW 1/4
Lease Owner Leben Drilling, Inc.
Lease Name Toothaker Well No. 1
Office Address 905 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 26 1956
Application for plugging filed November 26 1956
Application for plugging approved November 26 1956
Plugging commenced November 26 1956
Plugging completed November 26 1956
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	229'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up to 225'. Bottom Halliburton plug @ 225' with 15 sacks bulk cement. Top Halliburton plug @ 40' with 10 sacks bulk cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 - 1956
CONSERVATION DIVISION
Wichita, Kansas

12-1-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kan-Tex Drillers, Inc.
Address 413 Beacon Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Harvey E. Nightingale (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harvey E. Nightingale
413 Beacon Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29 day of November, 1956

My commission expires November 8, 1960

Frances E. Krenke
Notary Public.



PLUGGING
FILE SEC. 7 T 8 R 27W
ROCK PAGE 120 LINE 32

DRILLERS' LOG

No. 1 Toothaker
SE SE SW of Section 7-8S-27W
Sheridan County, Kansas

FROM	TO	
0	160	Surface, shale, shells
160	231	Sand, shells, Blue shale
231	1020	Shale and shells
1020	1590	Sand and shale
1590	2000	Shale and sand
2000	2350	Red Bed
2350	2390	Anhydrite
2390	2550	Shale and shells
2550	2775	Shale and Lime shells
2775	2910	Shale and lime
2910	2980	Shale, shells, lime streaks
2980	3105	Shale and shells
3105	3165	Shale and lime
3165	3905	Lime and shale
3905	3955	Lime
3955	4095	Lime and shale
4095	4185	Shale
4185	4225	Shale and lime streaks
4225	4430	Shale
4430	4480	Lime
	4480	Rotary Total Depth D & A

COMMENCED: 11-13-1956

COMPLETED: 11-26-1956

CASING RECORD:

Set 8 5/8" surface casing
at 229' with 185 sacks
bulk cement, 2% Calcium
Chloride.

STATE OF KANSAS)
)
COUNTY OF SEDGWICK) S S

I hereby affirm that the above and foregoing is a true and correct copy of the formations encountered on the No. 1 Toothaker, SE SE SW Section 7-8S-27W, Sheridan County, Kansas, as reflected by the daily drilling reports.

RECEIVED
STATE CORPORATION COMMISSION

KAN-TEX DRILLERS, INC.

12-1-56 DEC 1 - 1956


By: *Harvey E. Nightingale*
Harvey E. Nightingale

CONSERVATION DIVISION

Subscribed and sworn to, ~~Kansas~~ ^{Wichita, Kansas} me this 29 day of November, 1956

My Commission Expires: November 8, 1960

Frances E. Kroenke
Notary Public



PLUGGING
SEC. 7 T. 8 R. 27W
PAGE 120 LINE 32