

15-179-20372-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec 9 Twp. 8S Rge. (E) 27 (W)
Location as "NE/CNWxSWx" or footage from lines NE NE
Lease Owner National Oil Company
Lease Name JAMES Well No. 1
Office Address 200 W. Douglas, Suite 550, Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 7, 1974
Application for plugging filed (verbally) February 7, 1974
Application for plugging approved (verbally) February 7, 1974
Plugging commenced February 7, 1974
Plugging completed February 7, 1974
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4075 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set at 1440' w/110 cu. ft. cement
2nd plug set at 240' w/30 cu. ft. cement
3rd plug set at 40' w/10 cu. ft. cement
Plugging completed at 4:30 p.m. 2-7-74

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1974
CONSERVATION DIVISION
Wichita, Kansas

2-13-74

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of February, 1974

Beverly Mann
Notary Public.

My commission expires February 10, 1975

CONTRACTOR'S WELL LOG

OPERATOR: National Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: JAMES #1
 LOCATION: NE NE, Sec. 9-8S-27W
 Sheridan County, Kansas
 GEOLOGIST: George Dent
 SPUD DATE: January 31, 1974
 COMPLETION DATE: February 7, 1974

0	115	Clay
115	157	Sand
157	159	Rock
159	182	Sand
182	1314	Shale
1314	1961	Shale w/Sand Streaks
1961	2096	Sand
2096	2305	Sand and Shale
2305	2339	Anhydrite
2339	3052	Shale & Lime
3052	3815	Lime and Shale
3815	4075	Lime
	4075	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 13 1974
 CONSERVATION DIVISION
 Wichita, Kansas

2-13-74

Drilled 227' of 12½" surface hole. Set 8-5/8" surface csg. at 226' K.B. w/150 sx. quick set cement. Cement circulated. Plug down at 11:00 p.m. 1-31-74.
 Dry and Abandoned

<u>SAMPLE TOPS</u>		<u>ELEVATION</u>
Anhydrite	2303 (+ 329)	2632 K.B.
B/Anhydrite	2339 (+ 293)	2630 D.F.
		2624 G.L.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the JAMES #1, NE NE, Section 9-8S-27W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.
 By: *Jerry A. Langrehr*
 Jerry A. Langrehr
 Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 12th day of February, 1974.

Beverly Mann
 Beverly Mann, Notary Public

My Commission Expires:

February 10, 1975