


15-179-00065-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Sheridan County. Sec. 10 Twp. 8S Rge. 27W (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Leben Drilling, Inc.
Lease Name Mc Clelland Well No. 1
Office Address 905 Central Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-3-58 19
Application for plugging filed 7-3-58 19
Application for plugging approved 7-3-58 19
Plugging commenced 7-3-58 19
Plugging completed 7-3-58 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A.D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4025 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	288'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set at 600' with 25 sacks.
2nd plug set at 285' with 15 sacks.
topplug set at 40' with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of July, 1958

Rudolph G. Benjamin
Notary Public.

My commission expires June 17, 1961

RECEIVED
STATE CORPORATION COMMISSION
AUG 6 1958
CONSERVATION DIVISION
Wichita, Kansas

8-6-58

PLUGGING
FILE SEC 10 T 8 R 27W
BOOK PAGE 113 LINE 16

15-179-00065-00-00

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:
COMMENCED:
COMPLETED:

LEBEN DRILLING, INC.
LEBEN DRILLING, INC.
Mc CLELLAND #1
NE 1/4 NE 1/4 NE 1/4 SEC. 10-8S-27W
SHERIDAN COUNTY, KANSAS
6-24-58
7-3-58

0	40	Clay & Sand		
40	150	Sand		
150	240	Sand & Shale		
240	315	Shale	TOPS:	
315	1550	Shale & Sand	ANHYDRITE	2283
1550	1910	Shale & Lime Streaks	HEESNER	3752
1910	2065	Sand	TORONTO	3777
2065	2283	Shale & Redbed	LANSING-KC	3799
2283	2315	Anhydrite	BASE -KC	4012
2315	2575	Shale & Shells		
2575	3935	Shale & Lime	ELEVATION	2602 K.B.
3935	3995	Lime		
3995	4025	Lime & Shale		
	4025	<u>Rotary Total Depth - D & A</u>		

Set 288' of 8 5/8 surface casing with 185 sacks cement with 2 Gal & 4 CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Mc Clelland #1, located NE 1/4 NE 1/4 NE 1/4 Section 10, Township 8 South, Range 27 West, Sheridan County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By: Frank Hamlin
Frank Hamlin

STATE OF KANSAS }
COUNTY OF SEDGWICK } 55

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 21st day of July 1958.

Ruth E. Benjamin
Ruth E. Benjamin, Notary Public

My Commission Expires:
June 17, 1961

PLUGGING
FILE SEC 10 T 8 S 27W
BOOK PAGE 113 LINE 16